

2211 Congress Street Portland, ME 04122

Gensler

214 North Tryon Street Suite 2320 Charlotte, NC 28202 United States Tel 704.377.2725 Fax 704.377.2807

12/15/17 ISSUE FOR PERMIT & CONSTRUCTION



Unum Workplace Transformation - Phase 2 & 3 (HO2 & HO3)

Project Number 59.6481.003

Description

CONSTRUCTION PLAN - LEVEL 00 -EAST - HO2

As indicated

A02.100E.3

© 2015 Gensler

C. REFER TO SHEET A00.010 FOR PARTITION TYPE DETAILS. D. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS GOVERN. THE TYPE,

SHEET NOTES

INFORMATION.

MORE INFORMATION.

WALL LOCATIONS.

09 LINE OF CEILING ABOVE. TYPICAL.

32 OPERABLE PARITION, MODERN FOLD

23 PROVIDE HOLD OPEN DOOR HARDWARE WITH CONNECTION TO FIRE

ALARM, REFER TO DOOR SCHEDULE AND ELECTRICAL FOR MORE

24 PREP LANDINGS, TREADS, AND RISERS FOR FLOOR FINISH AS SCHEDULED THROUGHOUT. REFER TO FINISH PLANS AND LEGEND FOR

79 EXISTING ROOM TO REMAIN. PROVIDE PT-1 FINISH ALL EXPOSED GWB

- LOCATION, AND DIMENSIONS OF ALL PARTITIONS AND DOORS SHALL BE AS SHOWN ON ARCHITECT'S DRAWINGS. IN CASE OF CONFLICT, NOTIFY ARCHITECT PRIOR TO PARTITION INSTALLATION. ARCHITECTS PLAN SUPERSEDES ALL OTHERS.
- E. ALL PARTITIONS ARE DIMENSIONED FROM FINISHED FACE TO FINISHED FACE U.N.O. AND SHALL ALLOW FOR THICKNESS OF WALL FINISHES, INCLUDING WOOD AND FABRIC PANELS.
- AND AV EQUIPMENT.
- I. PERIMETER OFFICES ARE DIMENSIONED FROM INSIDE FACE OF SILL, U.N.O. J. CENTER ALL PERIMETER OFFICE PARTITIONS ON CENTERLINE OF WINDOW MULLION, U.N.O. SEE DETAIL 09/A08.100.
- K. ALL NEW WALLS TO BE LOCATED IN RELATION TO EXISTING WALLS TO REMAIN AND COLUMN LINES AS REQ'D. L PATCH AND REPAIR AND PREP FOR FINISH, ALL ABANDONED ELECTRICAL, DATA AND FIRE DEVICES.

— - — 1-HOUR RATED WALL ---- 2-HOUR RATED WALL EXISTING WALL

NOT IN CONTRACT