



GENERAL NOTES:

- COORDINATE THE EXACT LOCATION OF ALL THERMOSTATS WITH FINAL FURNITURE LAYOUT, EQUIPMENT LAYOUT, ARCH AND OWNERS REPRESENTATIVE. NEW TSTATS SHALL MATCH BASE BUILDING TSTATS IN EVERY RESPECT. CONTRACTOR SHALL THE NEW TSTATS INTO BUILDING EMS AND UPDATE IT ACCORDINGLY.
- ALL THERMOSTATS LOCATED ON WOOD AND/OR FEATURE WALLS SHALL BE BUTTON TYPE. SEE PLANS FOR EXACT LOCATIONS. COORDINATE WITH ARCHITECTS FINISH PLANS.
- THERE WILL BE NO LEAD ACID BATTERIES EXCEEDING A TOTAL OF 50 GALLONS OF ELECTROLYTE CAPACITY.
- ARCHITECTURAL DRAWINGS ARE TO BE USED FOR FINAL LOCATION OF DIFFUSERS, MECHANICAL PLAN DIFFUSER LOCATIONS ARE FOR REFERENCE ONLY.
- COORDINATE DIFFUSER SELECTIONS WITH CEILING TYPES AND ARCHITECTURAL FEATURES. SEE ARCHITECTURAL PLANS FOR ELEVATIONS AND MATERIALS.
- ALL BOXES SHALL BE LOCATED IN AN AREA THAT ALLOWS SERVICING.
- ALL HVAC CONTROLS MUST BE TIED INTO THE BUILDINGS' BAS SYSTEM.
- ALL DEMOLISHED HVAC EQUIPMENT WILL NOT BE DAMAGED DURING REMOVAL AND SHALL BE RETURNED TO THE OWNER. OWNER SHALL BE GIVEN PROPER NOTICE BEFORE TRANSFERRING EQUIPMENT.
- CONTRACTOR SHALL WALK FLOOR WITH OWNER TO ENSURE ALL BOXES WILL BE ACCESSIBLE ABOVE CEILING PRIOR TO CEILING INSTALLATION.
- ALL EXTERIOR THERMOSTATS SHALL BE INSULATED BEHIND TO AVOID INFILTRATION FROM EXTERIOR.
- CONTRACTOR SHALL PROVIDE A LINED RETURN AIR BOOT SIZED TO LIMIT THE MAXIMUM RETURN AIR VELOCITY TO NO MORE THAN 500 FEET PER MINUTE TO SERVE ANY ROOM WITH ALL WALLS TO DECK.

LEGEND NOTES:
(APPLY THIS SHEET ONLY)

- RELOCATE EXISTING THERMOSTAT TO NEW LOCATION SHOWN. COORDINATE WITH NEW FURNITURE LAYOUT AND ARCHITECT PRIOR TO INSTALLING IN NEW LOCATION.
- CONTRACTOR TO RELOCATE EXISTING PDU TO LOCATION SHOWN. RECONNECT, EXTEND EXISTING DUCT, HOT WATER SUPPLY AND RETURN PIPING FULL SIZE OF EXISTING. COORDINATE WITH DIV. 26. PATCH ALL HOLES IN DUCTWORK AIRIGHT W/ SHEET METAL AND "HARDCAST".
- CONTRACTOR SHALL REMOVE ALL INSULATION FROM SUPPLY DUCTWORK IN AREAS OPEN TO STRUCTURE. DUCTWORK SHALL BE PAINTED TO MATCH CEILING.
- ALL DUCTWORK WITHIN AREAS OPEN FROM FLOOR TO DECK SHALL BE ROUND PAINTGRIP SPIRAL DUCT. NO FLEX DUCT SHALL BE INSTALLED. COORDINATE COLOR OF DUCT WITH ARCHITECT.
- THERMOSTAT SHALL CONTROL MULTIPLE BOXES.
- DEMO EXISTING TERMINAL UNIT IN THIS AREA. CAP ALL HOT WATER LINES ABOVE CEILING AND REMOVE ALL DUCTWORK, CONTROLS, ETC. SEAL ANY OPENINGS IN DUCTWORK WITH SHEETMETAL AND "HARDCAST".
- REBALANCE EXISTING DIFFUSERS TO CFM INDICATED.

unum
2211 Congress Street
Portland, ME 04122

Gensler
214 North Tryon Street
Suite 2320
Charlotte, NC 28202
United States
Tel 704.377.2725
Fax 704.377.2807

BW & A
Brad J. Rabinowitz, P.E.
420 Mineral Lane
Charlotte, NC 28217
Tel 704.357.5333
MEP JOB# 170358

Date	Description
12.15.2017	ISSUE FOR PERMIT AND CONSTRUCTION

Seal / Signature

Project Name

Unum Workplace Transformation
- Phase 2 & 3 (HO2 & HO3)
Project Number
59.6481.003
Description
1ST FLOOR PLAN - HVAC

Scale

1ST FLOOR PLAN - HVAC
1/8"=1'-0"