



- GENERAL NOTES:**
- COORDINATE THE EXACT LOCATION OF ALL THERMOSTATS WITH FINAL FURNITURE LAYOUT, EQUIPMENT LAYOUT, ARCH AND OWNERS REPRESENTATIVE. NEW TSTATS SHALL MATCH BASE BUILDING TSTATS IN EVERY RESPECT. CONTRACTOR SHALL TIE NEW TSTATS INTO BUILDING EMS AND UPDATE IT ACCORDINGLY.
 - ALL THERMOSTATS LOCATED ON WOOD AND/OR FEATURE WALLS SHALL BE BUTTON TYPE. SEE PLANS FOR EXACT LOCATIONS. COORDINATE WITH ARCHITECTS FINISH PLANS.
 - THERE WILL BE NO LEAD ACID BATTERIES EXCEEDING A TOTAL OF 50 GALLONS OF ELECTROLYTE CAPACITY.
 - ARCHITECTURAL DRAWINGS ARE TO BE USED FOR FINAL LOCATION OF DIFFUSERS, MECHANICAL PLAN DIFFUSER LOCATIONS ARE FOR REFERENCE ONLY.
 - COORDINATE DIFFUSER SELECTIONS WITH CEILING TYPES AND ARCHITECTURAL FEATURES. SEE ARCHITECTURAL PLANS FOR ELEVATIONS AND MATERIALS.
 - ALL BOXES SHALL BE LOCATED IN AN AREA THAT ALLOWS SERVICING.
 - ALL HVAC CONTROLS MUST BE TIED INTO THE BUILDINGS' BAS SYSTEM
 - ALL DEMOLISHED HVAC EQUIPMENT WILL NOT BE DAMAGED DURING REMOVAL AND SHALL BE RETURNED TO THE OWNER. OWNER SHALL BE GIVEN PROPER NOTICE BEFORE TRANSFERRING EQUIPMENT.
 - CONTRACTOR SHALL WALK FLOOR WITH OWNER TO ENSURE ALL BOXES WILL BE ACCESSIBLE ABOVE CEILING PRIOR TO CEILING INSTALLATION.
 - ALL EXTERIOR THERMOSTATS SHALL BE INSULATED BEHIND TO AVOID INFILTRATION FROM EXTERIOR.
 - CONTRACTOR SHALL PROVIDE A LINED RETURN AIR BOOT SIZED TO LIMIT THE MAXIMUM RETURN AIR VELOCITY TO NO MORE THAN 500 FEET PER MINUTE TO SERVE ANY ROOM WITH ALL WALLS TO DECK.

- LEGEND NOTES:**
(APPLY THIS SHEET ONLY)
- RELOCATE EXISTING THERMOSTAT TO NEW LOCATION SHOWN. COORDINATE WITH NEW FURNITURE LAYOUT AND ARCHITECT PRIOR TO INSTALLING IN NEW LOCATION.
 - DEMO EXISTING TERMINAL UNIT IN THIS AREA. CAP ALL HOT WATER LINES ABOVE CEILING AND REMOVE ALL DUCTWORK, CONTROLS, ETC. SEAL ANY OPENINGS IN DUCTWORK WITH SHEETMETAL AND "HARDCAST".
 - THERMOSTAT SHALL CONTROL MULTIPLE BOXES.
 - RETURN AIR DUCT WORK SHALL BE EXTENDED TO GO FURTHER THAN NEW WALL PROVIDED AS SHOWN.
 - DEMO EXISTING DUCTWORK TO THE LOCATION INDICATED AND CAP. SEAL ANY OPENINGS IN DUCTWORK WITH SHEETMETAL AND "HARDCAST".
 - CONNECT NEW HWS & HWR PIPING TO EXISTING HWS & HWR PIPING IN THIS AREA.

4TH FLOOR PLAN -- HVAC
1/8"=1'-0"

unum
2211 Congress Street
Portland, ME 04122

Gensler
214 North Tryon Street
Suite 2320
Charlotte, NC 28202
United States
Tel: 704.377.2725
Fax: 704.377.2807

BW & A
Brad J. Rabinowitz, P.E.
420 Mianell Lane
Charlotte, NC 28217
Tel: 704.357.5333
MEP JOB# 170358

Date	Description
12.15.2017	ISSUE FOR PERMIT AND CONSTRUCTION

Seal / Signature

12/14/17

Project Name
Unum Workplace Transformation
- Phase 2 & 3 (HO2 & HO3)

Project Number
59.6481.003

Description
4TH FLOOR PLAN - HVAC

Scale

M2.104W