

- ROUTE 1/2" CW AND CONNECT WITH SHUT OFF VALVE TO ICE MAKER AND PROVIDE IN RECESSED BOX BELOW COUNTER. COORDINATE EXACT CONNECTION LOCATION WITH EQUIPMENT AND ARCHITECT AND ROUTE DRAIN TO HUB DRAIN IN THIS AREA. PROVIDE BACK FLOW PREVENTOR AS REQUIRED BY LOCAL AUTHORITY. BFP SHALL MEET ASSE 1022 IN ACCORDANCE WITH IPC 608.16.10.
- PROVIDE HUB DRAIN BELOW COUNTER IN READILY ACCESSIBLE LOCATION FOR ICE MAKER DRAIN. COORDINATE WITH MILLWORK CONTRACTOR TO ENSURE PROPER ACCESS TO DRAIN.
- ROUTE 1/2" CW AND CONNECT WITH SHUT OFF VALVE TO REFRIGERATOR. PROVIDE RECESSED BOX. COORDINATE EXACT CONNECTION LOCATION WITH EQUIPMENT AND ARCHITECT. PROVIDE BACK FLOW PREVENTOR AS REQUIRED BY LOCAL AUTHORITY.
- ROUTE 1/2" CW AND CONNECT WITH SHUT OFF VALVE TO COFFEE MAKER AND PROVIDE IN RECESSED BOX BELOW COUNTER AND COORDINATE EXACT PIPING ROUTING WITH ARCHITECT. PROVIDE BACK FLOW PREVENTOR AS REQUIRED BY LOCAL AUTHORITY. BFP SHALL MEET ASSE 1022 IN ACCORDANCE WITH IPC 608.16.10.
- DEMOLISH EXISTING DRINKING FOUNTAIN IN THIS LOCATION AND PROVIDE NEW ADA COMPLIANT DRINKING FOUNTAIN AS SPECIFIED ON SHEET PO.002. TIE NEW 3" W, 1½" AND ½" CW TO EXISTING SANITARY SEWER, VENT AND DOMESTIC WATER LINES OF EQUAL SIZE OR GREATER. COORDINATE EXACT CONNECTIONS WITH EXISTING CONDITIONS.
- $\overline{7}$ PIPING SHALL BE ON THE TENANT SIDE OF THE WALL AND NOT PENETRATE INTO THE STAIR WELL.



Gensler

214 North Tryon Street Tel 704.377.2725
Suite 2320 Fax 704.377.2807
Charlotte, NC 28202
United States



 △ Date
 Description

 12.15.2017
 ISSUE FOR PERMIT AND CONSTRUCTION

Seal / Signature



Unum Workplace Transformation
- Phase 2 & 3 (HO2 & HO3)

- Phase 2 & 3 (HO2 & HO3)

59.6481.003

Description

3RD FLOOR PLAN - PLUMBING

Scale

P3.103W

© 2017 Gensler