



CONCRETE FND WALL/BEAM SCHEDULE

MARK	SIZE	REINFORCING
EXT. WALL TYP UNO	8" THICK x CONT. CONC. WALL	#4 @ 16" O.C. HORIZ.
CW1	8" THICK x CONT. CONC. WALL	#4 @ 16" O.C. HORIZ. #4 @ 12" O.C. VERT.

CONCRETE FOOTING SCHEDULE

MARK	SIZE	FTG REINFORCING
TYPICAL CONT. STRIP FTG	10" THICK x 24" WIDE x CONT. STRIP FOOTING	(3) #4 CONT. -TYP. #4 HOOK DOWELS @ 32"
SF1	10" THICK x 3'-6" WIDE x CONT. OFFSET STRIP FOOTING	(5) #4 CONT. -TYP. #4 HOOK DOWELS @ 12"
F4	4'-0" SQ. x 12" THICK ISOLATED FTG	#4 @ 12" O.C. E.W. TOP & BOT MAT
F5	5'-0" SQ. x 12" THICK ISOLATED FTG	#4 @ 12" O.C. E.W. TOP & BOT MAT

- FOUNDATION PLAN**
- NOTES:
- ALL STRIP FOOTINGS ARE 10" DEEP 2'-0" WIDE x CONT. WITH (3) #4 BARS LONGITUDINAL, AND #4 CROSS TIES @ 32" O.C. TYP. UNO
 - STEP IN TOP OF FOUNDATION WALL IS INDICATED THIS: AND SHOWS LOWER SIDE OF WALL
 - SEE S1.0 FOR STRUCTURAL GENERAL NOTES
 - T.O. EXTERIOR FOOTING TO BE 4'-0" MIN BELOW GRADE T.O. FOOTINGS ARE INDICATED THIS: (XX'-XX")
 - T.O. INTERIOR FOOTING TO BE 1'-0" MIN BELOW T.O. SLAB - T.O. FOOTINGS ARE INDICATED THIS: (XX'-XX")
 - FOOTING ELEVATION CHANGE OR STEP IN TOP OF FOOTING IS INDICATED THIS: AND SHOWS LOWER FOOTING.

* ADD'L REINFORCING MAY BE REQUIRED IN PLAN OR SECTIONS.
* ALL WALLS TO HAVE (2) #5 HORIZ. CONT. AT TOP AND BOT -TYP.

* ADD'L REINFORCING MAY BE REQUIRED IN PLAN OR SECTIONS.

Prepared For:

Consulting Engineer:

ARCHETYPE
architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

CLARK
INSURANCE

Project:

Revisions:

Scale: AS NOTED

Date: 06 Oct. 2016

FOUNDATION PLAN

S1.1