SNOW DRIFT LOADING DIAGRAM

ENTRY CANOPY ROOF FRAMING PLAN

JEWEL BOX ROOF FRAMING PLAN

ROOF FRAMING PLAN

SCALE 1/8"=1'-0"

NOTES:

1. SEE SHEET S1.0 FOR GENERAL STRUCTURAL NOTES.
2. ROOF SHEATHING TO BE 5/8" -SEE GENERAL NOTES FOR ADDITIONAL INFORMATION.
3. WALL SHEATHING TO BE 7/16" -SEE GENERAL NOTES FOR ADDITIONAL INFORMATION.
4. ALL WOOD COLUMNS IN 2x6 WALLS SHALL BE (3) 2x6 AND IN 2x4 WALLS SHALL BE (3) 2x4, UNO.
5. ALL WOOD BEAMS ARE FLUSH, UNO.
6. TOP OF ALL STEEL BEAMS & COLUMNS SHALL BE REF. ELEV. 110'-10 1/2" TYP UNO. INDICATED AS [XXX'-XX"]. {SL} INDICATES SLOPING BEAM/GIRDER. SEE ENDS FOR CONTROL ELEVATIONS.
7. ALL HEADERS ARE (2) 2x8 BOX BEAM HEADERS, UNO.
8. ALL ELEVATIONS LISTED BASED OFF REFERENCE ELEVATION 100'-0" EQUAL TO USGS 69'-0".

FRAMING PLAN SYMBOLS KEY

□	WOOD POST
○	STEEL COLUMN
(X)	NUMBER OF WOOD STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
B	COLUMN BELOW
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
◄	JOIST BEARING
◄/	CONTINUOUS JOIST WITH INTERMEDIATE BEARING
⊢	FLUSH FRAMED JOIST BEARING WITH HANGER
	WOOD STUD BEARING WALL BELOW
	SHEAR WALL
"X"T	NUMBER OF TRIM STUDS UNDER HEADER
"X"K	NUMBER OF KING STUDS ADJACENT TO HEADER

Structural Integrity Consulting Engineers, Inc.
77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralinteg.com

BUILD WITH CONFIDENCE

© 2016 Structural Integrity Consulting Engineers, Inc.

SI # 15-0208

STATE OF MAINE AARON C. JONES No. 10958 LICENSED PROFESSIONAL ENGINEER

Date: 02/07/17

10/06/16

Prepared For:

Consulting Engineer:

Architect: ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project: CLARK INSURANCE

Revisions:

Scale: AS NOTED

Date: 06 Oct. 2016

FRAMING PLAN

S1.2