NOTES:
1. INSTALLATION SHALL NOT ALLOW INTER-TWINING OF CABLES.
2. DIRECT BURY ELECTRICAL CABLES MAY BE USED IF ALLOWED BY CENTRAL MAINE POWER.
3. CONFIRM CONDUIT SIZES WITH INDIVIDUAL UTILITY COMPANIES PRIOR TO INTALLATION.
4. COORDINATE FINAL LAYOUT WITH INDIVIDUAL UTILITY COMPANIES.

6 CABLE TRENCH SECTION

NOT TO SCALE

NOTE: COORDINATE INSTALLATION REQUIREMENTS WITH PORTLAND WATER DISTRICT

5 TYPICAL WATER MAIN SECTION

NOT TO SCALE

4 TYPICAL CATCH BASIN SECTION

NOT TO SCALE

12 STONE DRIPSTRIP SECTION

NOT TO SCALE

GENERAL NOTES FOR MANHOLES AND CATCH BASINS

1. ALL CONCRETE SHALL HAVE A MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF 4000 lbs. PER SQ. INCH AT THE END OF 28 DAYS, UNLESS OTHERWISE NOTED.
2. MANHOLES MAY BE CONSTRUCTED OF PRECAST REINFORCED CONCRETE, OR CAST IN PLACE.
3. PRECAST REINFORCED CONE BARREL MANUFACTURED PER ASTM SPEC. C-478.
4. ALL STORM AND SEWER MANHOLE COVERS SHALL BE SOLID AND SHALL HAVE ONE 7/8" DIAMETER DRILLED PICK HOLE LOCATED 8" FROM THE CENTER OF THE COVER.
5. ALL SANITARY MANHOLE COVERS SHALL HAVE "SEWER" CAST INTO THE COVER. ALL STORMWATER/DRAIN MANHOLE COVERS SHALL HAVE "DRAIN" CAST INTO THE COVER.
6. ALL MANHOLE RISERS SHALL BE ETHERIDGE 24" OR APPROVED EQUAL.
7. SEWER BRICK SHALL CONFORM TO ASTM SPEC. DESIGNATE ON C-32-63, GRADE MA AND SA.
8. ALL SANITARY MANHOLES SHALL HAVE A WATERPROOFING COATING APPLIED TO THE EXTERIOR SURFACE.
9. CATCH BASIN FRAMES FOR TYPE A4 CATCH BASIN CURB INLETS SHALL BE ETHERIDGE DR5A OR APPROVED EQUAL.
10. CASTINGS SHALL CONFORM TO ASTM DESIGNATION A48-CLASS 35.
11. EXISTING MANHOLES, CATCH BASINS, FRAMES, AND COVERS SHALL BE SALVAGED BY THE CONTRACTOR, AND SHALL REMAIN THE PROPERTY OF THE CITY OF PORTLAND.
12. ALL CATCH BASIN OUTLETS SHALL BE INSTALLED WITH A CASCO TRAP. SEE FIGURE II-09.

1 GENERAL NOTES FOR MANHOLES & CATCH BASINS (II-4)

NOT TO SCALE

8 JELLYFISH® FILTER DETAILS

NOT TO SCALE

NOTE: FOR ADD'L INFORMATION SEE DETAIL 4, SHEET C2.4

7 OVERFLOW & CATCHBASIN #8 DETAIL

NOT TO SCALE

NOTES:
1. ALTERNATIVE CONSTRUCTION METHODS OR PAYMENT METHODS SHALL BE APPROVED IN ADVANCE BY THE CITY.
2. IN PAVED AREAS, DEPTHS OF GRAVEL AND HOT MIX ASPHALT PAVEMENT SHALL MATCH THE GREATER OF EXISTING CONDITIONS OR THE REQUIREMENTS FOR THE CORRESPONDING STREET CLASSIFICATION.
3. DIMENSION **B** SHALL BE SUFFICIENT TO ALLOW CRUSHED STONE BEDDING TO BE PLACED AND COMPACTED UNDER THE HAUNCHES OF THE PIPE; BUT IN ALL CASES DIMENSION **B** SHALL BE AT LEAST 9".
4. DIMENSION **A** IS THE MAXIMUM WIDTH ALLOWED FOR CALCULATING PAY QUANTITIES UNDER GRANULAR BORROW, CRUSHED STONE, STRUCTURAL EARTH EXCAVATION, AND STRUCTURAL ROCK EXCAVATION. DIMENSION **A** SHALL BE BASED ON PIPE DIAMETER **D**, AS SET FORTH IN THE FOLLOWING TABLE.

PIPE DIAMETER, D (INCHES)	MAX. TRENCH WIDTH, A (FEET)
4	4.0
6	4.0
8	4.0
10	4.0
12	5.0
15	5.0
18	5.0
21	5.0
24	6.0
27	6.0
30	6.0
36	6.0
42	7.0
48	7.0

2 TYPICAL PIPE TRENCH INSTALLATION (II-12) IN CONGRESS STREET

NOT TO SCALE

NOTE: EXISTING MANHOLE OR CATCH BASIN SHALL BE CORE DRILLED FOR PIPE INSTALLATION. IF PIPE DIAMETER IS SO LARGE THAT CORE DRILLING IS PROHIBITED, THE CONTRACTOR MAY SAW CUT THE STRUCTURE TO CREATE PIPE OPENING. THE NEW OPENING MUST THEN BE SEALED AND WATERTIGHT BOTH INSIDE AND OUTSIDE THE STRUCTURE.

11 GAS PIPING TRENCH SECTION

NOT TO SCALE

NOTES:
1. CONSTRUCT LEVEL LIP AND SPREADER ON ZERO PERCENT GRADE.
2. DO NOT CONSTRUCT LEVEL SPREADER ON FILL.
3. STORM RUNOFF CONVERTED TO SHEET FLOW SHALL OUTLET ONTO STABILIZED AREA. WATER SHALL NOT BE CHANNELIZED IMMEDIATELY BELOW POINT OF DISCHARGE.

10 LEVEL SPREADER SECTION

NOT TO SCALE

9 TYPICAL TRENCH SECTION - ON SITE

NOT TO SCALE

NOTE:
REMOVE WATERPROOFING FROM STRUCTURE BEFORE APPLYING MORTAR. WATERPROOF AGAIN AFTER MORTAR HAS SET.

METHOD 3 - NEW PIPE INTO EXISTING STRUCTURE

3 PLASTIC PIPE CONNECTION METHODS (II-14)

NOT TO SCALE

PINKHAM & GREER
CIVIL ENGINEERS
28 WARREN AVE., PORTLAND, ME. 04103
TEL: 207.797.5242 FAX: 207.797.4245

STATE OF MAINE
THOMAS GREER
No. 4206
LICENSED
PROFESSIONAL ENGINEER
8/22/16

Reviewed for Code Compliance
Inspection Division
Department of Public Services
Date: 02/07/17

REV.	DATE	DESCRIPTION
2	8/25/16	REV'D PER CITY REVIEW COMMENTS
1	7/11/16	REV'D DRAINAGE SYSTEM, REV'D PER REVIEW COMMENTS

NORTHLAND ENTERPRISES, LLC
17 SOUTH STREET
PORTLAND, MAINE 04101

SCALE: AS SHOWN
DATE: JUNE 17, 2016
PROJECT: 13151
DRN BY: RJS
DESG BY: TSG
CHK BY: TSG

1945 CONGRESS STREET
ELKS LODGE, PORTLAND, MAINE

DETAILS

C2.4

MAP/LOT 216-A-6 & 217-A-1