Structural Integrity
Consulting Engineers, Inc.
77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralinteg.com

BUILD WITH CONFIDENCE

© 2016 Structural Integrity Consulting Engineers, Inc.

SI # 15-0208

STATE OF MAINE
AARON C. JONES
No. 10958
LICENSED
PROFESSIONAL ENGINEER
10/06/16

Date: 02/07/17

CONCRETE FND WALL/BEAM SCHEDULE

MARK	SIZE	REINFORCING
EXT. WALL TYP UNO	8" THICK x CONT. CONC WALL	#4 @ 16" O.C. HORIZ. #4 @ 18" O.C. VERT.
* CW1 *	8" THICK x CONT. CONC WALL	#4 @ 16" O.C. HORIZ. #4 @ 12" O.C. VERT.

* ADD'L REINFORCING MAY BE REQUIRED IN PLAN OR SECTIONS.
* ALL WALLS TO HAVE (2) #5 HORIZ. CONT. AT TOP AND BOT -TYP.

CONCRETE FOOTING SCHEDULE

MARK	SIZE	FTG REINFORCING
TYPICAL CONT. STRIP FTG	10" THICK x 24" WIDE x CONT. STRIP FOOTING	(3) #4 CONT. -TYP. #4 HOOK DOWELS @ 32"
* SF1 *	10" THICK x 3'-6" WIDE x CONT. OFFSET STRIP FOOTING	(5) #4 CONT. -TYP. #4 HOOK DOWELS **@ 12"**
F4	4"-0" SQ. x 12" THICK ISOLATED FTG	#4 @ 12" O.C. E.W. TOP & BOT MAT FTG
F5	5"-0" SQ. x 12" THICK ISOLATED FTG	#4 @ 12" O.C. E.W. TOP & BOT MAT FTG

* ADD'L REINFORCING MAY BE REQUIRED IN PLAN OR SECTIONS.

FOUNDATION PLAN

SCALE 1/8"=1'-0"

NOTES:

1. ALL STRIP FOOTINGS ARE 10" DEEP 2'-0"" WIDE x CONT. WITH (3) # 4 BARS LONGITUDINAL, AND #4 CROSS TIES @ 32" O.C. TYP. UNO
2. STEP IN TOP OF FOUNDATION WALL IS INDICATED THUS: , AND SHOWS LOWER SIDE OF WALL.
3. SEE S1.0 FOR STRUCTURAL GENERAL NOTES
4. T.O. EXTERIOR FOOTING TO BE 4'-0" MIN BELOW GRADE T.O. FOOTINGS ARE INDICATED THUS: (XX'-XX")
5. T.O. INTERIOR FOOTING TO BE 1'-0" MIN BELOW T.O. SLAB - T.O. FOOTINGS ARE INDICATED THUS: (XX'-XX")
6. FOOTING ELEVATION CHANGE OR STEP IN TOP OF FOOTING IS INDICATED THUS: , AND SHOWS LOWER FOOTING.

Prepared For:

Consulting Engineer:

Architect: ARCHETYPE Architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project: CLARK INSURANCE

Revisions:

Scale: AS NOTED

Date: 06 Oct. 2016

FOUNDATION PLAN

S1.1