DOOR SCHEDULE

DOOR No.	LOCATION	DOOR W	DOOR H	DOOR THCK	DOOR TYPE	DOOR MAT'L	DOOR FINISH	FRAME THRESHOLD	FRAME MAT'L	FRAME FINISH	LABEL	OPER.	SWEEP	CL.	REMARKS
1ST FLOOR PLAN															
01	OFFICE	6'-0"	7'-0"		2	AL		ALUM	STOREFRONT		-	ENTR	Yes	Yes	
02	OFFICE	3'-0"	7'-0"	1 3/4"	3	I.G.	PTD	ALUM	HM	PTD	-	EXIT	Yes	Yes	PROVIDE EGRESS DOOR HARDWARE, TYP CLAPBOARD TRIM
03	SPRINKLER ROOM	3'-0"	7'-0"	1 3/4"	1	I.G.	PTD	ALUM	HM	PTD	-	STOR	Yes	Yes	TYP CLAPBOARD TRIM
04	ELECTRICAL ROOM	3'-0"	7'-0"	1 3/4"	1	I.G.	PTD	ALUM	HM	PTD	-	STOR	Yes	Yes	TYP CLAPBOARD TRIM
05	OFFICE	3'-0"	7'-0"	1 3/4"	3	I.G.	PTD	ALUM	HM	PTD	-	EXIT	Yes	Yes	PROVIDE EGRESS DOOR HARDWARE
06	ELECTRICAL ROOM	3'-0"	7'-0"	1 3/4"	1	HM	PTD	ALUM	HM	PTD	60 MIN	STOR	Yes	Yes	
07	SPRINKLER ROOM	3'-0"	7'-0"	1 3/4"	1	HM	PTD	ALUM	HM	PTD	60 MIN.	STOR	Yes	Yes	

1 LEAF TYPES
1/4" = 1'-0"

NOTES

1. ALL RATED DOORS TO HAVE CLOSERS, SMOKE SEALS, AND DOOR SWEEPS
2. ALL EXTERIOR DOORS TO HAVE CLOSERS, WEATHERSTRIPPING, AND DOOR SWEEPS
3. ALL DOORS ARE TO BE PAINT-GRADE, U.N.O.

LICENSED ARCHITECT DAVID LLOYD NO. 936 STATE OF MAINE Date: 02/07/17

Reviewed for Code Compliance Inspections Division Portland, Maine

Prepared For: NORTHLAND MANAGEMENT P.O. Box 7486 Portland, ME 04112

Consultant:

Architect: ARCHETYPE architects 48 Union Wharf Portland, Maine 04101 (207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: CLARK INSURANCE 1945 CONGRESS ST PORTLAND, ME 04102

Revisions:

Scale: 1/4" = 1'-0"

Date: 06 OCT 2016

DOOR SCHEDULE

A8.01