NOTES:
1. WINDOW DIMENSIONS ARE TO R.O.
2. T = TEMPERED GLAZING

5 STOREFRONT AND WINDOW ELEVATIONS
1/4" = 1'-0"

PUBLIC AREA DOOR SCHEDULE

DOOR No.	SIZE WIDTH	SIZE HEIGHT	SIZE THICKNESS	DOOR TYPE	DOOR MATERIAL	FINISH	THRESH	FRAME MATERIAL	LABEL	CLOSER	REMARKS
GRADE											
001	6'-0"	7'-0"		1	AL		AL	STOREFRONT		Yes	
002	3'-0"	7'-0"	1 3/4"	3	INSUL-GALV	PTD	AL	EXISTING		Yes	VERIFY SIZE IN FIELD
003	3'-6"	7'-0"	1 3/4"	3	INSUL-GALV	PTD	AL	EXISTING		Yes	VERIFY SIZE IN FIELD
004	3'-0"	7'-0"		2	AL		AL	STOREFRONT		Yes	
005	3'-0"	7'-0"		2	AL		AL	STOREFRONT		Yes	
006	3'-0"	6'-6"		2	AL		AL	EXISTING		Yes	VERIFY SIZE IN FIELD
007	6'-0"	7'-0"		1	AL		AL	STOREFRONT		Yes	

NOTE: COORDINATE ALL HARDWARE WITH OWNER

2 DOOR LEAF ELEVATIONS
1/4" = 1'-0"

ORDER OF INSTALLATION OF
WATER PROOFING AT WINDOWS.
WATER PROOFINGAT STOREFRONT AND DOORS USE STEPS 1-3

NOTES:
1. INSTALL AIR INFILTRATION BARRIER IN ORDER AS SHOWN BY NUMBERS.
2. IF APPLICABLE, LEAVE RELEASE PAPER ON LOWER HALF OF SILL FLASHING UNTIL FUTURE TIE-IN.
3. INSTALL FLASHING AND AIR INFILTRATION BARRIER TO FORM WATER SHEDDING LAPS
4. COORDINATE WITH FLASHING REQUIREMENTS OF WINDOW MANUFACTURER
5. FOLLOW MANUFACTURES RECOMMENDATIONS FOR INSTALLATION.

1 ORDER OF INSTALLATION OF WATERPROOFING AT WINDOWS
3/8" = 1'-0"

4 TYPICAL WINDOW SECTION
3" = 1'-0"

LICENSED ARCHITECT
DAVID LLOYD
NO. 936
STATE OF MAINE
Date: 05/02/17

Prepared For:
Northland Management
Address
City, State

Consultant:

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project:
Elks Lodge
Portland, Maine

Revisions:

Scale: As indicated

Date: 01/26/2017

DOOR AND WINDOW SCHEDULE

A8.02