NOTES:

1. SOUND CAULK WALL TRACK FOR ALL OFFICES.
2. ELEC OUTLETS ON EACH SIDE OF WALL TO BE OFFSET A MIN OF 1'-0".
3. WALLS INDICATED TO BE RATED ARE TO HAVE 5/8" "TYPE X" GWB EACH SIDE.
4. PROVIDE FIRE TREATED BLOCKING AS REQUIRED FOR ALL WALL MOUNTED EQUIPMENT AND FURNITURE.
5. PROVIDE 5/8" GYP BOARD TO UNDERSIDE OF DECK AT INTERIOR SIDE OF ALL EXISTING EXTERIOR WALLS
6. WHERE INDICATED, WALL FRAMING TO ALIGN WITH FRAMING ABOVE SO THAT GYP WALL FINISH IS FLUSH FOR ENTIRE HEIGHT OF WALL

1 INTERIOR FIT-OUT PLAN
1/8" = 1'-0"

REVISED WALL AND DOOR TAGS

LICENSED ARCHITECT DAVID LLOYD NO. 936 STATE OF MAINE
Date: 07/26/17

Prepared For: NORTHLAND MANAGEMENT, Address, City, State

Consultant:

Architect: ARCHETYPE architects, 48 Union Wharf Portland, Maine 04101, (207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: CLARK INSURANCE, 1945 CONGRESS ST, PORTLAND, ME 04102

Revisions:

3	1/25/17	TI Addendum 1
4	2/1/17	TI Addendum 2
5	2/3/17	TI Addendum 3
6	3/6/17	TI Addendum 4

Scale: 1/8" = 1'-0"

Date: Jan 19 2017

INTERIOR FIT OUT PLAN

A1.05