DOOR SCHEDULE

DOOR No.	LOCATION	DOOR W	DOOR H	DOOR THCK	DOOR TYPE	DOOR MAT'L	DOOR FINISH	FRAME THRESHOLD	FRAME MAT'L	FRAME FINISH	LABEL	OPER.	SWEEP	CL.	REMARKS
FIRST FLOOR PLAN															
01	VESTIBULE	6'-0"	7'-0"		2	AL		ALUM	STOREFRONT		-	ENTR	Yes	Yes	
02	MUD ROOM	3'-0"	8'-5"	1 3/4"	4	I.G.	PTD	ALUM	HM	PTD	-	EXIT	Yes	Yes	PROVIDE EGRESS DOOR HARDWARE, TYP CLAPBOARD TRIM
03	SPRINKLER ROOM	3'-0"	7'-0"	1 3/4"	1	I.G.	PTD	ALUM	HM	PTD	-	STOR	Yes	Yes	TYP CLAPBOARD TRIM
04	ELECTRICAL ROOM	3'-0"	7'-0"	1 3/4"	1	I.G.	PTD	ALUM	HM	PTD	-	STOR	Yes	Yes	TYP CLAPBOARD TRIM
05	MEETING	3'-0"	7'-0"	1 3/4"	3	I.G.	PTD	ALUM	HM	PTD	-	EXIT	Yes	Yes	PROVIDE EGRESS DOOR HARDWARE
06	ELECTRICAL ROOM	3'-0"	7'-0"	1 3/4"	1	HM	PTD	ALUM	HM	PTD	60 MIN	STOR	Yes	Yes	
07	SPRINKLER ROOM	3'-0"	7'-0"	1 3/4"	1	HM	PTD	ALUM	HM	PTD	60 MIN.	STOR	Yes	Yes	
101	RECEPTION/WAITING	6'-0"	8'-5"	1 3/4"	2	GLASS	-	ALUM	STOREFRONT	-	-	PASSAGE	Yes	Yes	
104	RECEPTION/WAITING	3'-0"	8'-5"	1 3/4"	1	GLASS		ALUM	HM	PTD		PASSAGE			
104A	MEETING	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
105	CHAIR/TABLE STORAGE	3'-0"	8'-0"	1 3/4"	7	WOOD									BARN DOOR
106	W.C.	3'-0"	7'-0"	1 3/4"	1	WOOD		ALUM	HM	PTD		PVCY	Yes	Yes	
109	MEETING	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
110	MEETING	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
111	MEETING	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
115	WOMEN	3'-0"	7'-0"	1 3/4"	1	WOOD		ALUM	HM	PTD		PASSAGE	Yes	Yes	
116	JANITOR	3'-0"	7'-0"	1 3/4"	1	WOOD		ALUM	HM	PTD		STOR	Yes	Yes	
117	MEN	3'-0"	7'-0"	1 3/4"	1	WOOD		ALUM	HM	PTD		PASSAGE	Yes	Yes	
118	SOLO	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
119	HUDDLE	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
120	HUDDLE	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
121	SOLO	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
123	OFFICE	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		OFFICE			
124	HUDDLE	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
125	OFFICE	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		OFFICE			
128	SOLO	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
129	SOLO/ LACTATION	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
130	IT SERVER	3'-0"	8'-5"	1 3/4"	1	WOOD		ALUM	HM	PTD		STOR	Yes	Yes	
131	CORRIDOR	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
132	TRAINING	3'-0"	8'-5"	1 3/4"	1	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
132A	CORRIDOR	3'-0"	8'-5"	1 3/4"	1	WOOD		ALUM	STOREFRONT	BRUSHED		PASSAGE			
133	CORRIDOR	3'-0"	8'-5"	1 3/4"	1	WOOD		ALUM	HM	PTD		PASSAGE			
133A	STORAGE	3'-0"	8'-0"	1 3/4"	7	WOOD									BARN DOOR
134	BREAKOUT	3'-0"	8'-5"	1 1/2"	5	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
135	COLLAB-CAFE	3'-0"	8'-5"	1 1/2"	5	ALUM		ALUM	STOREFRONT	BRUSHED		PASSAGE			
136	MUD ROOM	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE	Yes	Yes	
136A	MUD ROOM	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE	Yes	Yes	
137	FITNESS ROOM	3'-0"	8'-5"	1 3/4"	4	GLASS		ALUM	STOREFRONT	BRUSHED		PASSAGE			
138	FITNESS ROOM	3'-0"	7'-0"	1 3/4"	1	WOOD		ALUM	HM	PTD		PASSAGE	Yes	Yes	
139	FITNESS ROOM	3'-0"	7'-0"	1 3/4"	1	WOOD		ALUM	HM	PTD		PASSAGE	Yes	Yes	

SEE ID DRAWINGS FOR STOREFRONT ELEVATIONS

NOTES

1. ALL RATED DOORS TO HAVE CLOSERS, SMOKE SEALS, AND DOOR SWEEPS
2. ALL EXTERIOR DOORS TO HAVE CLOSERS, WEATHERSTRIPPING, AND DOOR SWEEPS
3. ALL DOORS ARE TO BE PAINT-GRADE, U.N.O.

1 LEAF TYPES
1/4" = 1'-0"

W1	W2
3 5/8"	6"

NON-RATED NON-BEARING ACOUSTICAL PARTITION
DESIGN NUMBER - N/A

1. **CONT. METAL FLOOR AND CEILING RUNNER -** CHANNEL SHAPED 3 5/8" 25 MSG STEEL WITH 1 1/4" LONG LEGS FASTENERS @ 2'-0" O.C. MAX. WITHIN 1" OF ENDS
2. **STEEL STUDS -** CHANNEL SHAPED 25 MSG STEEL 3 5/8" STUDS SPACED MAX. 24" O.C. RUNT TO 2" ABOVE FINISHED CEILING(**USE 6" STUD AT W2 WALLS)**
3. **GYPSUM BOARD -** (1) LAYER 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING, PAPER SURFACED, APPLIED PERPENDICULAR TO FRAMING WITH 1" TYPE S STEEL SCREWS SPACED 8" O.C.. SEE NOTES FOR GYP. BD. TYPE
4. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED
5. **SEALANT -** ACOUSTIC SEALANT BOTH SIDES.
6. **BLOCKING - (NOT SHOWN)** WOOD BLOCKING AS NEEDED
7. **TAPE AND COMPOUND - (NOT SHOWN)** VINYL, DRY OR PREMIXED JOINT COMPOUND, APPLIED IN TWO COATS TO JOISTS AND SCREW HEADS, PAPER TAPE, 2 IN. WIDE, EMBEDDED IN FIRST LAYER OF COMPOUND OVER ALL JOINTS.
8. **BASE -** SEE FINISH SCHEDULE
9. UNDERSIDE OF STRUCTURE
10. TOP OF STRUCTURE
11. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED- RUN BATT OVER TOP OF WALL FOR 3' ON EACH SIDE BETWEEN ADJACENT OFFICES, SOLO, HUDDLE AND CONFERENCE ROOMS

2 WALL TYPE 1 & 2
1 1/2" = 1'-0"

W3 **NON-RATED NON-BEARING ACOUSTIC PARTITION**

1. **STUDS -** CHANNEL-SHAPED, MIN 3-5/8" WIDE BY 1-1/4" DEEP WITH 5/16" FOLDED BACK RETURN FLANGE LEGS. FABRICATED FROM NO. 25 MSG GALV STEEL. MAX STUD SPACING 24" O.C. STUDS TO BE CUT 1" LESS THAN ASSEMBLY HEIGHT.
2. **CEILING RUNNER -** CHANNEL-SHAPED TOP TRACK, MIN. 3 5/8" WIDE BY 1 1/4" DEEP, FABRICATED FROM NO. 20 MSG GALV STEEL. TOP TRACK SITS INSIDE VERTICALLY SLOTTED HEAD TRACK, ATTACHED TO CEILING WITH FASTENERS, 24" O.C. MAX. GYPSUM AND VERTICAL STUDS FASTENED TO TOP TRACK ONLY
3. **TYPE X GYPSUM BOARD -** (1) LAYER PROPRIETARY 5/8" TYPE X GYP. BD. EACH SIDE. APPLIED PERPENDICULAR TO STUDS WITH 1" TYPE S DRYWALL SCREWS 8" O.C. AT VERT. JNTS AND INTERMEDIATE STUDS AND 12" O.C. AT TOP AND BOTTOM RUNNER. SEE NOTES FOR GYP. BD. TYPE (STAGGER GYP. BD. JNTS 24" ON NON-FURRED SIDE.) SEAL GYP BOARD TO TRUSS WITH FIRE CAULKING. **USE TYPE MRX GYP BD AT TOILET/LOCKER ROOMS.**
4. **CAULKING AND SEALANTS -** A BEAD OF ACOUSTICAL SEALANT APPLIED AROUND THE PARTITION PERIMETER FOR SOUND CONTROL, BOTH SIDES OF WALL.
5. **BLOCKING - (NOT SHOWN)** WOOD BLOCKING AS NEEDED
6. **TAPE AND COMPOUND - (NOT SHOWN)** VINYL, DRY OR PREMIXED JOINT COMPOUND, APPLIED IN TWO COATS TO JOISTS AND SCREW HEADS, PAPER TAPE, 2 IN. WIDE, EMBEDDED IN FIRST LAYER OF COMPOUND OVER ALL JOINTS.
7. **SAFB SOUND INSULATION**
8. **FLOOR RUNNER -** CHANNEL-SHAPED RUNNERS, MIN. 3 5/8" WIDE W/ DEEP LEGS, FABRICATED FROM NO. 20 MSG GALV STEEL. ATTACHED TO FLOOR WITH FASTENERS, 24" O.C. MAX.

3 WALL TYPE 3
1 1/2" = 1'-0"

W4 **NON-RATED NON-BEARING ACOUSTIC PARTITION**

1. **STUDS -** CHANNEL-SHAPED, MIN 6" WIDE BY 1-1/4" DEEP WITH 5/16" FOLDED BACK RETURN FLANGE LEGS. FABRICATED FROM NO. 25 MSG GALV STEEL. MAX STUD SPACING 24" O.C. STUDS TO BE CUT 1" LESS THAN ASSEMBLY HEIGHT.
2. **CEILING RUNNER -** CHANNEL-SHAPED TOP TRACK, MIN. 6" WIDE BY 1 1/4" DEEP, FABRICATED FROM NO. 20 MSG GALV STEEL. TOP TRACK SITS INSIDE VERTICALLY SLOTTED HEAD TRACK, ATTACHED TO CEILING WITH FASTENERS, 24" O.C. MAX. GYPSUM AND VERTICAL STUDS FASTENED TO TOP TRACK ONLY
3. **TYPE X GYPSUM BOARD -** (1) LAYER PROPRIETARY 5/8" TYPE X GYP. BD. EACH SIDE. APPLIED PERPENDICULAR TO STUDS WITH 1" TYPE S DRYWALL SCREWS 8" O.C. AT VERT. JNTS AND INTERMEDIATE STUDS AND 12" O.C. AT TOP AND BOTTOM RUNNER. SEE NOTES FOR GYP. BD. TYPE (STAGGER GYP. BD. JNTS 24" ON NON-FURRED SIDE.) SEAL GYP BOARD TO TRUSS WITH FIRE CAULKING. **USE TYPE MRX GYP BD AT TOILET/LOCKER ROOMS.**
4. **CAULKING AND SEALANTS -** A BEAD OF ACOUSTICAL SEALANT APPLIED AROUND THE PARTITION PERIMETER FOR SOUND CONTROL, BOTH SIDES OF WALL.
5. **BLOCKING - (NOT SHOWN)** WOOD BLOCKING AS NEEDED
6. **TAPE AND COMPOUND - (NOT SHOWN)** VINYL, DRY OR PREMIXED JOINT COMPOUND, APPLIED IN TWO COATS TO JOISTS AND SCREW HEADS, PAPER TAPE, 2 IN. WIDE, EMBEDDED IN FIRST LAYER OF COMPOUND OVER ALL JOINTS.
7. **SAFB SOUND INSULATION**
8. **FLOOR RUNNER -** CHANNEL-SHAPED RUNNERS, MIN. 6" WIDE W/ DEEP LEGS, FABRICATED FROM NO. 20 MSG GALV STEEL. ATTACHED TO FLOOR WITH FASTENERS, 24" O.C. MAX.
9. **ROOF SHEATHING ON WOOD TRUSS** - REFERENCE WALL AND BUILDING SECTIONS FOR ADD'L ROOF INFORMATION.

4 WALL TYPE 4
1 1/2" = 1'-0"

W5	W6
3 5/8"	6"

1. **CONT. METAL FLOOR AND CEILING RUNNER -** CHANNEL SHAPED 3 5/8" 25 MSG STEEL WITH 1 1/4" LONG LEGS FASTENERS @ 2'-0" O.C. MAX. WITHIN 1" OF ENDS
2. **STEEL STUDS -** CHANNEL SHAPED 25 MSG STEEL 3 5/8" STUDS SPACED MAX. 24" O.C. RUNT TO 2" ABOVE FINISHED CEILING(**USE 6" STUD AT W2 WALLS)**
3. **GYPSUM BOARD -** (1) LAYER 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING, PAPER SURFACED, APPLIED PERPENDICULAR TO FRAMING WITH 1" TYPE S STEEL SCREWS SPACED 8" O.C.. SEE NOTES FOR GYP. BD. TYPE
4. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED
5. **SEALANT -** ACOUSTIC SEALANT BOTH SIDES.
6. **BLOCKING - (NOT SHOWN)** WOOD BLOCKING AS NEEDED
7. **TAPE AND COMPOUND - (NOT SHOWN)** VINYL, DRY OR PREMIXED JOINT COMPOUND, APPLIED IN TWO COATS TO JOISTS AND SCREW HEADS, PAPER TAPE, 2 IN. WIDE, EMBEDDED IN FIRST LAYER OF COMPOUND OVER ALL JOINTS.
8. **BASE -** SEE FINISH SCHEDULE
9. UNDERSIDE OF STRUCTURE
10. TOP OF STRUCTURE
11. **SOUND ATTENUATION BATT -** FIBERGLASS BATT WITH UL CLASS AS TO SURFACE BURNING CHARACTERISTICS AND OR FIRE RESISTANCE REQUIRED-

5 WALL TYPE 5 &6
1 1/2" = 1'-0"

LICENSED ARCHITECT DAVID LLOYD NO. 936 STATE OF MAINE
Date: 07/26/17

Prepared For: NORTHLAND MANAGEMENT, P.O. Box 7486, Portland, ME 04112

Consultant:

Architect: ARCHETYPE architects, 48 Union Wharf Portland, Maine 04101, (207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: CLARK INSURANCE, 1945 CONGRESS ST, PORTLAND, ME 04102

Revisions:

Scale: As indicated

Date: Jan 19 2017

DOOR SCHEDULE & WALL TYPES

A8.01