

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

PORTLAND LODGE #188 BPOE OF USA

Located at

1945 CONGRESS ST

PERMIT ID: 2017-00930

ISSUE DATE: 06/22/2017

CBL: 216 A006001

has permission to **Minor interior renovations - new floor, ACT ceiling, electrical work, HVAC, and bathroom renovation.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.	A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
---	---

/s/ Jason Grant

/s/ Doug Morin

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Elks Club

Building Inspections

Use Group: A-2/B/S-1 **Type:** 5B
Assembly Bar - Occupant load = 235
Assembly Banquet Hall - Occupant
Load = 358
Business
Storage
Total Occupancy = 634
Sprinkled
1st Floor
MUBEC/IBC 2009

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Plumbing Under Slab
Close-in Plumbing/Framing
Electrical Close-in
Final - Commercial
Final - Electric

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit		Permit No: 2017-00930	Date Applied For: 06/13/2017	CBL: 216 A006001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Elks Club	Proposed Project Description: Minor interior renovations - new floor, ACT ceiling, electrical work HVAC, and bathroom renovation.			
<hr/>				
Dept: Zoning	Status: Approved w/Conditions	Reviewer: Ann Machado	Approval Date: 06/21/2017	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.				
<hr/>				
Dept: Building Inspecti	Status: Approved w/Conditions	Reviewer: Doug Morin	Approval Date: 06/22/2017	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) The addition of plumbing fixtures,including water lines, drainage and vent piping shall be installed in compliance with the UPC 2015 code.				
2) The addition of plumbing fixtures,including water lines, drainage and vent piping shall be installed in compliance with the UPC 2009 code.				
3) Wiring installations for this project or occupancy shall comply with the 2014 National Electric Code. Existing conditions for new occupancies will be required to be upgraded to prescribed standards. Loading calculations may need to be provided prior to any electrical installations. Please contact the City electrical inspectors with any questions.				
4) Per IBC Sec. 1006.1 Means of Egress shall be provided with illumination				
5) This project includes alterations that Maine state law requires for compliance with the 2010 ADA Standards for Accessible Design.				
6) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
<hr/>				
Dept: Engineering DPS	Status: Not Applicable	Reviewer: Rachel Smith	Approval Date: 06/19/2017	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) This approval is non-applicable to Engineering DPW as it relates to approval for Grease Control Equipment for the Fats, Oil, and Grease Program. If approval is needed for this project by the Engineering Department of Public Works for any other reason than FOG, please contact 207-874-8801.				
<hr/>				
Dept: Fire	Status: Approved w/Conditions	Reviewer: Jason Grant	Approval Date: 06/19/2017	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) Per 2009 NFPA 101 section 12.7.9.3 and 13.7.9.3 every room constituting an assembly occupancy (50+ people) and not having fixed seating shall have the occupancy load of the room posted on a sign in a conspicuous place by the main entrance to the space.				
2) The means of egress shall be illuminated and marked in accordance with 2009 NPFA 101, sections 7.8 and 7.10. 7.8.1.3 The minimum illumination of the egress path for stairs shall be at least 10 ft-candle and the minimum illumination of the egress path of floors and other walking surfaces other than stairs shall be at least 1 ft-candle. Emergency Lighting in accordance with 2009 NPFA 101, sections 7.9 shall be provided				
3) Fire extinguishers are required per NFPA 1 (2009 Edition) Table 13.6.2. The quantity, size, type and location shall be in accordance with NFPA 1, 13.6.8. For light or ordinary hazard buildings a 2-A rated extinguisher (5lb. Dry Chemical Ext.) is required no more than 75 feet of travel distance from anywhere in the building and at least 1 extinguisher per story. A wet chemical class K fire extinguisher is needed within 30' of travel distance for the kitchen hood system.				

- 4) City of Portland Code Chapter 10 section 10-18 (h) All structures with a life safety signaling system (fire alarm) or a fire suppression system (sprinkler) shall have a Knox Box. All keys required to access the building and operate the fire alarm or suppression system shall be maintained in the box.
- 5) This review has determined that your project requires fire sprinkler system. A separate City of Portland Water-Based Fire Suppression System Permit is required for all new sprinkler systems, including standpipe systems, and sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.
- 6) This review has determined that your project requires fire alarm system. A separate City of Portland Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.
- 7) All construction shall comply with City Code, Chapter 10.
All construction shall comply with 2009 NFPA 101 Life Safety Code, Chapter # 43 and other applicable chapters
All construction shall comply with 2009 NFPA 1, Fire Code.
This review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code. NFPA 1 (section 1.14.4).
All means of egress to remain accessible at all times.
If applicable, all outstanding code violations shall be corrected prior to final inspection.