Inspectional Division
Date: 11/20/17

EXHAUST FANS

TAG	MANUFACTURER	MODEL #	CFM	VOLTS	MCA	NOTES
EF-1	GREENHECK	G-95	600 @ 0.5	120	7	
EF-2	GREENHECK	G-95	600 @ 0.5	120	7	
EF-3	PANASONIC	FV-08	80 @ 0.1	120	1.1	
EF-4	BROAN	L250	261 @ 0.1	120	2.1	
BF-1	SUNCOURT	TF104	200	120	2.5	RUN ON LINE VOLTAGE SENSOR AT PANEL
BF-2	SUNCOURT	TF105	200	120	2.5	LTAGE SENSOR AT PANEL

SPLIT SYSTEM

TAG	MFG	MODEL	VOLTAGE	MCA	MAX FUSE	HEATING BTU	COOLING BTU	NOTES
AH-1	FIRST CO.		120	10	-	60,000	36,000	
CU-1	TRANE	4TTAO36	208/3	18	-	-	36,000	
CU-2	DAIKEN	RKN24	208/230/1	18.3	20	-	24,000	
DS-1	DAIKEN	FTK24	*	*	*	-	-	*POWER FROM CU-2

RTU

TAG	MFG	MODEL	VOLT/PHASE	MCA	COOLING BTU	HEATING BTU (INPUT)	CFM	ACCESSORIES	NOTES
RTU-1A	TRANE	YSC102	208/3	43.3	102,000	120,000	3400	(ALL) ECONOMIZER, BUILT IN DISCONNECT, UNPOERED GFI, POWER EXHAUST	
RTU-2A	TRANE	YSC102	208/3	43.3	102,000	120,000	3400		
RTU-1B	TRANE	YSC092	208/3	39.3	94,000	120,000	3000		
RTU-2B	TRANE	YSC092	208/3	39.3	94,000	120,000	3000		

PUMPS

TAG	MANUFACTURER	MODEL #	VOLTS	MCA	GPM	NOTES
P-1	GRUNDFOS	UPS-26-99	115	1.8	18 @ 8'	
P-2	GRUNDFOS	UPS-32-100	115	1.7	35 @ 14'	

BOILER

TAG	MANUFACTURER	MODEL #	VOLTS	MCA	BTU INPUT	E.F.F.	NOTES
B-1	NTI	TFT 200	115	12	200,000	95%	

ELECTRIC WALL HEATERS

TAG	MANUFACTURER	MODEL #	VOLTAGE	PHASE	WATTS	NOTES
EWH-1	STIEBEL ELTRON	CK-20E	208	1	2000	INTERNAL STAT
EWH-2	STIEBEL ELTRON	CK-20E	208	1	2000	INTERNAL STAT
EWH-3	STIEBEL ELTRON	CK-20E	208	1	2000	INTERNAL STAT
EWH-4	STIEBEL ELTRON	CK-20E	208	1	2000	INTERNAL STAT
EWH-5	STIEBEL ELTRON	CK-20E	208	1	2000	INTERNAL STAT
EWH-6	STIEBEL ELTRON	CK-20E	208	1	2000	INTERNAL STAT

Design • Build • Install • Service
HVAC SERVICES, INC.
73 BRADLEY DRIVE
WESTBROOK, MAINE 04092
(207) 854-HVAC (4822)

REVISIONS

NO. NOTES

PROJECT: DR. BEDECS
1945 CONGRESS ST. PORTLAND, MAINE

SHEET TITLE: MECHANICAL SCHEDULES

SCALE: N/A
DATE: 4-3-2017
DRAWN BY: TJF
SHEET No. M-5
CHECKED BY:
PRINT TO SCALE: 36x24