

FRAMING PLAN SYMBOLS KEY

■	WOOD POST
○	STEEL COLUMN
(x)	NUMBER OF WOOD STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
◄	JOIST BEARING
/	CONTINUOUS JOIST WITH INTERMEDIATE BEARING
⊢	FLUSH FRAMED JOIST BEARING WITH HANGER
▒	WOOD STUD BEARING WALL BELOW
"X"T	NUMBER OF TRIM STUDS UNDER HEADER
"X"K	NUMBER OF KING STUDS ADJACENT TO HEADER

1 / S1.4 ROOF FRAMING PLAN
1/8" = 1'-0"

0' 2' 10' 20'

NOTES:

1. SEE SHEET S1.0 FOR GENERAL STRUCTURAL NOTES
2. ALL WOOD COLUMNS IN 2x6 WALLS SHALL BE (3) 2x6 AND IN 2x4 WALLS SHALL BE (3) 2x4 UNLESS NOTED OTHERWISE ON PLANS
3. ALL BEAMS ARE FLUSH, UNO
4. ALL HEADERS IN 2x BEARING WALLS ARE (2) 2X8, UNO
5. ALL ROOF TRUSSES TO BE 14" (MID SPAN) MONO-SLOPE P.E. ROOF TRUSSES @ 16" W/ LSL RIM -TYP UNO
6. ROOF SHEATHING TO BE 5/8" T+G, SEE GENERAL NOTES FOR ADDITIONAL INFORMATION -TYP
7. ALL TRUSS TO TRUSS CONNECTIONS BY MANUFACTURER - TYP UNO.
8. TRUSS DESIGNER TO COORIDINATE TRUSS LAYOUT WITH FLOOR OPENING, PLUMBING, AND UTILITY REQUIREMENTS - TYP.

STATE OF MAINE
AARON C. JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
12/27/2016

Inspection Division
Date: 11/20/17

Prepared For: Owner

Consultant: Structural Integrity Consulting Engineers
79 Fox Street
Portland, ME 04101
P. 207-797-7430
www.structuralintegrity.com
BUILDING STRUCTURAL ENGINEERS
Rev. 1 Rev. 2 Rev. 3 Rev. 4
S1#16-0203

Architect: ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022ARCHETYPE@ARCHETYPEPA.COM

Project: MEDICAL OFFICES
1945 CONGRESS STREET, PORTLAND MAINE

Revisions:

1	4/10/17	Revision 1
2	5/8/17	Col & Bm Adjusts

Scale: 1/8" = 1'-0"

Date: 27 Dec. 2016

ROOF FRAMING PLAN

S1.4