



**Interior Door Schedule**

Location	Size	Swing	Room Size
Closet	5/0 x 6/8	Bifold	N/A
Bath	2/6 x 6/8	RH	8' - 4" x 9' - 5" (+/-)
Bedroom	5/0 x 6/8	RH/LH	18' - 6" x 14' - 0" (+/-)
Hall			4' - 0" x 8' - 4" (+/-)
Play-Rm			18' - 6" x 27' - 4" (+/-)

REF: ICC-2015-IRC Page 63 R311.1 & 311.6 = Minimum Egress

PRODUCT CODE/U-FACT	SIZE	COUNT	R.O. SIZE
TW3046 / 0.25	3'-1 5/8" X 4'- 8 7/8"	1	3'-2 1/8" x 4'-9 3/8"
AN321 / 0.26	5'-11 5/8" X 2'-0 1/8"	3	6'-0 1/8" x 2'-0 5/8"

REF: ICC-2015-IRC Page 456 Table N1102.1.2 (R402.1.2)

**Insulation Schedule**

Location	Const.	Int.R-Value	Ext. Clad
Dormer Walls	2x6	R-21	Vinyl/Insulated
Rafter/Ceiling	2x10	R-30C	Existing
Gable Ends	2x6	R-21	Existing
Attic	N/A	R-49 (+/- Max)	Existing
Floor	Existing	Existing	N/A

REF: ICC-2015-IRC Page 456 Table N1102.1.2 (R402.1.2)

CIR Enterprises

Customer: Stanford Brown  
 Site: 3 Heritage Court, Portland, ME 04102

Discription:

Note: Framing crew to confirm rough openings on site.  
 Adjust sufficient to accommodate installation  
 and insulation/vapor barrier applications.

Project: Proposed Dormer Layout

Date: 9/29/15

Drawing: **FP -1**