



Interior Door Schedule			
Location	Size	Swing	Room Size
Closet	5/0 x 6/8	Bifold	N/A
Bath	2/6 x 6/8	RH	8' - 4" x 9' - 5" (+/-)
Bedroom	5/0 x 6/8	RH/LH	18' - 6" x 14' - 0" (+/-)
Hall			4' - 0" x 8' - 4" (+/-)
Play-Rm			18' - 6" x 27' - 4" (+/-)

REF: ICC-2015-IRC Page 63 R311.1 & 311.6 = Minimum Egress

PRODUCT CODE/ U-FACT	SIZE	COUNT	R.O. SIZE
TW3046 / 0.25	3'-1 5/8" X 4'- 8 7/8"	2	3'- 2 1/8" x 4'-9 3/8"
AN321 / 0.26	5'- 11 5/8" X 2'- 0 1/8"	3	6'-0 1/8" x 2'-0 5/8"

REF: ICC-2015-IRC Page 456 Table N1102.1.2 (R402.1.2)

Insulation Shedule (Including New Dormer)					
Location	Const.	Int.R-Value	Ext. Clad	Clad @ Dormer	
Dormer Walls	2x6	R-21	Vinyl/Insulated		
Rafter/Ceiling	2x10	R-30C	Existing	Existing	Asphalt Shingles
Ext - Walls	2x6	R-21	Existing	Existing	
Attic	N/A	R-49 (+/- Max)	Existing	Existing	
Floor	Existing	Existing	Existing	N/A	

REF: ICC-2015-IRC Page 456 Table N1102.1.2 (R402.1.2)

CIR Enterprises	Discription:	Project: Proposed Dormer Layout
Customer: Stanford Brown Site: 3 Heritage Court, Portland, ME 04102	Note: Framing crew to confirm rough openings on site. Adjust sufficient to accommodate installation and insulation/vapor barrier applications.	Date: 9/29/15
		Drawing: <b>FP -1</b>