



Soffit/Fascia duplicated onsite = Lower Eave
 Closest possible as required to accommodate
 Soffit/Propa Venting.

Sheathing : 1/2 Ply c/w sheathing clips

Roofing:

- Drip edge @ perimeter
- Ice and Water Shield @ perimeter
- Roof Top Guard @ field
- Ashault shingle - Matching Existing

Dormer Support Off Existing Roof = 48-in.

Wall Construction (Dormer)

- 2x6 SPF KD #2 or Better
- 1/2-inch Advantech Sheathing
- Typar Vapor Barrier
- Insulated Vinyl Siding - Matching Existing

FASTENERS:

- 12D/16D NAILS ON FRAMING CONSTRUCTION AS APPLICABLE
- 8D RING SHANK NAILS ON FLOOR SHEATHING
- 8D NAILS ON WALL AND ROOF SHEATHING
- 1 1/4" ALUMINIUM NAILS FOR VINYL SIDING

<p>CIR Enterprises</p> <p>Customer: Stanford Brown</p> <p>Site: 3 Heritage Court, Portland, ME 04102</p>	<p>Discription:</p> <p>Project: Proposed Dormer Layout</p> <p>Date: 9/29/15</p> <p>Drawing: D3</p>
--	--