Soffit/Fascia duplicated onsite = Lower Eve
Closest possible as required to accommodate
Soffit/Propa Venting.

Sheathing : 1/2 Ply c/w sheathing clips

Roofing:
- Drip edge @ perimeter
- Ice and Water Shield @ perimeter
- Roof Top Guard @ field
- Ashault shingle - Matching Existing

Dormer Support Off Existing Roof = 48-in.

Wall Construction (Dormer)
- 2x6 SPF KD #2 or Better
- ½-inch Advantech Sheathing
- Typar Vapor Barrier
- Insulated Vinyl Siding - Matching Existing

FASTENERS:
12D/16D NAILS ON FRAMING CONSTRUCTION AS APPLICABLE
8D RING SHANK NAILS ON FLOOR SHEATHING
8D NAILS ON WALL AND ROOF SHEATHING
1 1/4" ALUMINIUM NAILS FOR VINYL SIDING

CIR Enterprises	Discription:	Project: Proposed D
Customer: Stanford Brown Site: 3 Heritage Court, Portland, ME 04102		Date: 9/29/15
		Drawing: D3

Date: 03/07/16

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

CITY OF PORTLAND, MAINE
RESURGAM