



2 LIFE SAFETY PLAN
 SCALE: 1/8" = 1'-0"
 2' 4' 8' 16'

AREA NOT IN CONTRACT

IBC 2009 CODE DATA	
SUITE FLOOR AREA	3,940 SF
NUMBER OF STORIES	2ND OF 3
USE AND OCCUPANCY CLASSIFICATION - CHAPTER 3	B BUSINESS USE
TYPE OF CONSTRUCTION - TABLE 601	II-B
FIRE RESISTANT CONSTRUCTION - TABLE 601:	
STRUCTURAL FRAME	0 HOUR
EXTERIOR BEARING WALLS	0 HOUR
INTERIOR BEARING WALLS	0 HOUR
EXTERIOR NONBEARING WALLS	0 HOUR
INTERIOR NONBEARING WALLS	0 HOUR
FLOOR CONSTRUCTION	0 HOUR
ROOF CONSTRUCTION	0 HOUR
FIRE RATING STAIR ENCLOSURES - SECTION 1022.1	1 HOUR
SPRINKLER SYSTEM REQUIRED - SECTION 903	REQUIRED
FIRE ALARM SYSTEM REQUIRED - SECTION 907	REQUIRED
OCCUPANT LOAD - TABLE 1004.1.1	40
MAXIMUM COMMON PATH OF TRAVEL DISTANCE - NFPA 101-2009 TABLE A7.6	100 FEET
MAXIMUM EXIT TRAVEL DISTANCE - TABLE 1016.1	300 FEET
FIRE RATED CORRIDORS - TABLE 1018.1	N/A
DEAD END CORRIDOR LENGTH - SECTION 1018.4	50 FEET
MINIMUM NUMBER OF EXITS - TABLE 1021.2	2 PER FLOOR
FIRE EXTINGUISHERS	1 AT EACH EXIT 3-A 10-B-C
NOTES	

NFPA 101 2009 CODE DATA	
SUITE FLOOR AREA	3,940 SF
NUMBER OF STORIES	2ND OF 3
USE GROUP CLASSIFICATION - SECTION 3.3.178	SEE PLAN
TYPE OF CONSTRUCTION - NFPA 220	II (000)
FIRE RESISTANT CONSTRUCTION - NFPA 220:	
EXTERIOR BEARING WALLS	0 HOUR
INTERIOR BEARING WALLS	0 HOUR
COLUMNS	0 HOUR
BEAMS, GIRDERS, TRUSSES, AND ARCHES	0 HOUR
FLOOR CONSTRUCTION	0 HOUR
ROOF CONSTRUCTION	0 HOUR
EXIT STAIR ENCLOSURES - SECTION 7.1.3.2.1	1 HOUR
OCCUPANT LOAD - TABLE 7.3.1.2	40
PROTECTION OF VERTICAL OPENINGS - SECTION 12.3.1	N/A
MINIMUM NUMBER OF EXITS - TABLE A7.6	2 PER FLOOR
DEAD END CORRIDOR LENGTH - TABLE A7.6	50 FEET
MAXIMUM COMMON PATH OF TRAVEL DISTANCE - TABLE A7.6	100 FEET
MAXIMUM EXIT TRAVEL DISTANCE - TABLE A7.6	300 FEET
FIRE ALARM SYSTEM REQUIRED - SECTION 12.3.4.1.1	REQUIRED
SPRINKLER SYSTEM REQUIRED - SECTION 12.3.5	REQUIRED
FIRE RATED CORRIDORS - SECTION 12.3.6	N/A
FIRE EXTINGUISHERS	1 AT EACH EXIT 3-A 10-B-C
NOTES	

- LIFE SAFETY PLAN KEY**
- EXIT SIGN
 - EMERGENCY LIGHT
 - FIRE EXTINGUISHER
 - FIRE ALARM PULL STATION
 - FIRE ALARM STROBE
 - FIRE ALARM HORN STROBE
 - 90' TRAVEL DISTANCE
 - 90' EXIT SEPARATION

