FINISH NOTES:		
DETAIL	HATCH	DESCRIPTION
CPT-1T	NO HATCH	SHAW CONTRACT GROUP: BLACK TEA STYLE #600C3 MHS TILE: COLOR #500: MONOLITHIC ALONG LONGEST WALL
VCT-1		ARMSTRONG EXCELON, STERLING, 51904. 1/4 TURN INSTALL
LVT-1		SHAW COMMERCIAL HARD SURFACE HIGH PERFORMANCE LUXURY TILE, STYLE JEOGORI 02151V, COLOR 00500 LINEN (ASHLAR INSTALL)
1	PROVIDE FROSTING ON ALL FULL-LITE GLASS DOORS OR SIDELIGHTS. FROSTING TO BE THREE FOOT HIGH, POSITIONED WITH THE TOP AT 5'-6 AFF, AS SHOWN IN DE-2. FROSTING TO BE 4' HIGH ON DOORS LARGER THAN 7'.	
2	REFINISH EXISTING CABINETS TO MATCH NEW CABINET FINISH (WILSONART DESIGNER WHITE D354) AND REPLACE COUNTER WITH NEW PLAM COUNTER (WILSONART DESIGNER WHITE D354).	
1	ALL PAINT BASE TO BE SHERWIN WILLIAMS SUPERPAINT. PROMAR 200 CAN NOT BE USED.	
2	GC TO CONFIRM CARPET IS MANUFACTURED FROM THE SAME DIE LOT.	
3		

1 FINISH PLAN

SCALE: 1/4" = 1'-0"

1' 2' 4' 8'

AREA NOT IN CONTRACT

PLAN NORTH

© 2017 Michael R. Charek, Architect

Reviewed for Code Compliance
Inspections Division
Portland, Maine

Date: 12/12/17

Michael Charek Architects

25 Hartley Street
Portland, Maine 04103
(207) 761-0556

REGISTERED ARCHITECT
MICHAEL R. CHAREK
No. 1174
STATE OF MAINE

Offices for Maxim Healthcare Services

Second Floor
1685 Congress Street, 2nd Floor
Portland, ME 04102

Title

FINISH PLAN

Scale: 1/4" = 1'-0"

Date: 11/16/17

Revisions

ISSUED FOR PERMIT

Sheet

A6