

## DOOR SCHEDULE

DOOR		Style	NOTES
MARK	SIZE WD HGT		
1	3'-0" 6'-8"	Hinged - Single (Existing)	--
2	3'-0" 6'-10"	Cased Opening	--
3	2'-6" 6'-8"	Hinged - Single (Existing)	--
4	2'-6" 7'-0"	born type slider	--
5	2'-6" 6'-8"	Hinged - Single (Existing)	--
6	6'-0" 6'-8"	Bifold - Double (Existing)	--
7	6'-0" 6'-10"	Sliding - Double - Full Lite	--
8	2'-8" 6'-10"	Hinged - Single - Full Lite	--
9	2'-6" 6'-10"	Fixed - Single - Screen	--
10	2'-6" 6'-8"	Standard (existing)	--
11	2'-4" 6'-8"	Pocket - Single	--
12	2'-6" 6'-8"	born type slider	--
13	2'-6" 6'-8"	born type slider	--
14	2'-8" 6'-8"	born type slider	--
15	6'-0" 6'-8"	Sliding - Double - Full Lite	Integrity Wood/Ulfirex

**WINDOW NOTES:**

ALL WINDOWS SHALL BE LOW E, ARGON FILLED INSULATING GLASS.

ALL WINDOWS TO HAVE A U-FACTOR RATING OF 0.30 OR BETTER.

ALL WINDOW GRILLES SHALL BE SIMULATED DIVIDED LITE.

ALL GLAZING SHALL CONFORM TO IRC 2012 R308

WINDOW GLAZING WITH SILL HTS LESS THAN 18" TO BE TEMPERED.

WINDOW GLAZING 24" OR CLOSER TO DOORS SHALL BE TEMPERED.

WINDOW GLAZING 36" OR CLOSER TO STAIRWAYS AND 36" OR LESS

ABOVE FLOOR SHALL BE TEMPERED.

WINDOW GLAZING WITHIN 60" OF THE BOTTOM OF A STAIRWAY AND LESS

THAN 36" ABOVE THE FLOOR SHALL BE TEMPERED.

ALL WINDOWS SHALL CONFORM TO R312.2 WINDOW FALL PROTECTION

ALL WINDOWS WITH SILL HTS LESS THAN 24" AND MORE THAN 72" ABOVE

GRADE TO HAVE OPENING LIMITERS TO RESTRICT OPENING TO 4"

R310 EMERGENCY ESCAPE AND RESCUE OPENINGS

SLEEPING ROOMS SHALL HAVE AT LEAST ONE EGRESS WINDOW WITH A

SILL HT OF NOT MORE THAN 44" A MINIMUM CLEAR OPENING HEIGHT OF

24" AND A MINIMUM CLEAR OPENING WIDTH OF 20"

## WINDOW SCHEDULE

MARK	SIZE		Style	Head Height	NOTES
	WIDTH	HEIGHT			
1	2'-0"	2'-3"	Awning	6'-8"	Integrity Wood/Ulfirex
2	2'-4"	3'-6"	Casement	9'-0"	Existing
3	5'-11 1/2"	3'-6"	Glider	6'-9"	Integrity Wood/Ulfirex
4	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
5	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
6	2'-6"	5'-0"	Casement	6'-10"	Integrity Wood/Ulfirex
7	2'-6"	5'-0"	Casement	6'-10"	Integrity Wood/Ulfirex
8	2'-6"	5'-0"	Casement	6'-10"	Integrity Wood/Ulfirex
9	4'-6"	5'-0"	Casement - Double	6'-10"	Integrity Wood/Ulfirex
10	2'-0"	2'-3"	Awning	6'-8"	Integrity Wood/Ulfirex
11	1'-11 3/4"	3'-5"	Casement	6'-8"	Existing
12	3'-5 1/4"	3'-5"	Casement - Double	6'-8"	Existing
13	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
14	2'-6"	2'-4"	Awning	9'-2"	Integrity Wood/Ulfirex
15	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
16	2'-6"	2'-4"	Awning	9'-2"	Integrity Wood/Ulfirex
17	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
18	2'-6"	2'-4"	Awning	9'-2"	Integrity Wood/Ulfirex
19	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
20	2'-6"	2'-4"	Awning	9'-2"	Integrity Wood/Ulfirex
21	2'-6"	4'-6"	Casement	6'-10"	Integrity Wood/Ulfirex
22	2'-6"	2'-4"	Awning	9'-2"	Integrity Wood/Ulfirex
23	2'-6"	4'-6"	Casement	6'-8"	Integrity Wood/Ulfirex
24	2'-6"	4'-6"	Casement	6'-8"	Integrity Wood/Ulfirex
25	2'-6"	4'-6"	Casement	6'-8"	Integrity Wood/Ulfirex
26	2'-6"	6'-0"	Casement	6'-8"	Integrity Wood/Ulfirex
27	2'-0 3/4"	4'-6"	Casement	6'-8"	Existing

PROSPECT



DESIGN

58 FOST ST. PORTLAND, ME  
www.prospectdesign.me  
T. 207.749.7400

SCHEDULES

SILVERMAN

DATE: 8.18.2014

DRAWN BY: BB

A-6.1