

ROOM FINISH SCHEDULE											
NO	ROOM NAME	FLOOR MATERIAL	BASE MATERIAL	WALLS				PAINT TYPE	CEILING		REMARKS
				NORTH	EAST	SOUTH	WEST		MATERIAL	HEIGHT	
100	SDS/GRANUFLO	-	-	-	-	-	-	-	-	REMARK: 2	
101	MEDICAL WASTE - NIC	-	-	-	-	-	-	-	-	-	
102	STORAGE	-	-	-	-	-	-	-	-	REMARK: 2	
103	FMC CORRIDOR	VCT1, 2, 3	RB2	P1, WP1	P1, WP1	P1, WP1	P1, WP1	ACT-1	8'-6"	REMARKS: 3, 4	
104	TECH REPAIR - NIC	-	-	-	-	-	-	-	-	-	
105	STORAGE	-	-	-	-	-	-	-	-	REMARKS: 3	
117	CORRIDOR	-	-	-	-	-	-	-	-	REMARKS: 1	
136	WIRING CLOSET	-	-	-	-	-	-	-	-	REMARKS: 3	
137	WATER TREATMENT	-	-	-	-	-	-	-	-	REMARKS: 1	
138	FMC CORRIDOR	VCT1, 2, 3	RB2	P1, WP1	P1, WP1	P1, WP1	P1, WP1	ACT-1	8'-6"	REMARKS: 3, 4	
139	CHIEF TECHNICIAN OFFICE	VCT1, 2, 3	RB2	P1	P1	P1	P1	ACT-1	8'-6"	-	
140	MEDICAL RECORDS	VCT1	RB2	P1	P1	P1	P1	ACT-1	8'-6"	-	
141	FMC CORRIDOR	VCT1, 2, 3	RB2	P1, WP1	P1, WP1	P1, WP1	P1, WP1	ACT-1	8'-6"	REMARKS: 3, 4	
142	STORAGE	RF1	RB3	WP2, P1 ABOVE	WP2, P1 ABOVE	WP2, P1 ABOVE	WP2, P1 ABOVE	ACT-2	10'-0"	-	
143	BUILDING COMMON EXIT CORRIDOR	VCT1, 2, 3	RB2	P1	P1	P1	P1	P5-GWB	EXIST	-	
144	COATS	VCT1, 2, 3	RB2	P1	P1	P1	P1	P5-GWB	EXIST	-	
145	VESTIBULE	MAT1	RB1	P1	P1	P1	P1	P5-GWB	EXIST	-	
146	FMC OPEN OFFICE	SV1	RB2	P1	P2	P1	P1	ACT-1	10'-0"	-	
147	SOCIAL WORKER OFFICE	VCT1, 2, 3	RB2	P2	P1	P1	P1	ACT-1	8'-6"	-	
148	GENERAL OFFICE	VCT1, 2, 3	RB2	P2	P1	P1	P1	ACT-1	8'-6"	-	
149	DIETITIAN OFFICE	VCT1, 2, 3	RB2	P2	P1	P1	P1	ACT-1	8'-6"	-	
150	EDUCATION OFFICE	VCT1, 2, 3	RB2	P1	P1	P1	P1	ACT-1	8'-6"	-	
151	SECRETARY OFFICE	VCT1, 2, 3	RB2	P1	P1	P1	P1	ACT-1	8'-6"	-	
152	AREA MANAGER'S OFFICE	VCT1, 2, 3	RB2	P1	P1	P1	P1	ACT-1	8'-6"	-	

COUNTERTOPS/ CASEWORK SCHEDULE					
NO	ROOM NAME	COUNTERTOPS/ CASEWORK			REMARKS
		HORIZONTAL SURFACES	VERTICAL SURFACES		
146	FMC OPEN OFFICE	SS1	PL1		

- ABBREVIATIONS:**
- CPT = CARPET
 - VCT = VINYL COMPOSITION TILE
 - VCT-ST = STATIC DISSIPATIVE VINYL COMPOSITION TILE
 - VT = VINYL TILE
 - SV = SHEET VINYL
 - CONC-S = CONCRETE SEALER
 - CONC-EP = EPOXY PAINTED CONCRETE
 - MAT = WALK OFF MAT
 - WCT = CERAMIC WALL TILE
 - P = PAINT FINISHES
 - GWB = GYPSUM WALL BOARD OR SUSPENDED GWB @ CEILING CONDITIONS. GWB TYPE VARIES, REFERENCE PARTITION SCHEDULE.
 - ACT-1 = 24 X 48 ACOUSTICAL CEILING TILE
 - ACT-2 = 24 X 24 ACOUSTICAL CEILING TILE
 - PT = PORCELAIN TILE
 - PTB = PORCELAIN TILE BASE
 - PL = PLASTIC LAMINATE
 - P-LAM = PLASTIC LAMINATE
 - RF = RESINOUS FLOOR
 - RFB = RESINOUS FLOOR BASE
 - VWC = VINYL WALL COVERING
 - WP = WALL PROTECTION

- NOTES:**
- REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 - REFERENCE DRAWINGS A2.0 & A2.3 FOR ADDITIONAL INFORMATION.
 - REFERENCE DRAWINGS A6.0-A6.5 FOR ADDITIONAL INFORMATION.

- REMARKS:**
- REPLACE ANY CEILING TILE AND GRID COMPONENTS DAMAGED BY THE NEW WORK INSTALLATIONS.
 - PATCH AND REPAIR EXISTING WALL SURFACES DAMAGES DURING THE INSTALLATION PROCESS. TOUCH-UP PAINT ALL REPAIRS.
 - PATCH AND REPAIR GWB SURFACES AT NEW WALL LOCATIONS. PAINT FINISH NEW WALLS AND TIE-INTO EXISTING SURFACES.
 - PROVIDE WALL PROTECTION TO 4'-0" AFF WITH TOP CAP AND BUTT JOINT, P1 ABOVE.

1 ROOM FINISH SCHEDULE
A2.8 SCALE: N.T.S.

KEY SCHEDULE				DOOR & DOOR FRAME SCHEDULE										
LOCKSET TYPE	KEYING SYSTEM	DOOR NO.	ROOM NO.	HARDWARE SET NO.	DOOR			FRAME				FIRE RATING	REMARKS	
					SIZE	MAT	TYPE	MAT	TYPE	HEAD DETAIL	JAMB DETAIL			SILL DETAIL
PASSAGE SET	NON-KEYED LOCKSET	105	105	H.W. SET #32A	4'-0" x 7'-0" x 1 3/4"	SCW	NV	HM	A	CWS-1/A2.7	CWS-2/A2.7			
PASSAGE SET	NON-KEYED LOCKSET	137	137	H.W. SET #32A	4'-0" x 7'-0" x 1 3/4"	SCW	NV	HM	A	CWS-1/A2.7	CWS-2/A2.7			
PASSAGE SET	NON-KEYED LOCKSET	138	138	H.W. SET #32A	4'-0" x 7'-0" x 1 3/4"	SCW	NV	HM	A	CWS-1/A2.7	CWS-2/A2.7	45 MIN		
OFFICE FUNCTION	GM M SM	139	139	H.W. SET #24A	3'-0" x 7'-0" x 1 3/4"	SCW	F	HM	A	CWS-1/A2.7	CWS-2/A2.7			
OFFICE FUNCTION	GM M SM	140	140	H.W. SET #33B	3'-0" x 7'-0" x 1 3/4"	SCW	F	HM	A	CWS-1/A2.7	CWS-2/A2.7	45 MIN		
TOUCH LOCK	GM M	141	141	H.W. SET #36	EXISTING	EXIST	EXIST					60 MIN	SEE REMARK #1	
PANIC	GM M	K1	142A	H.W. SET #20	(PAIR) 3'-0" x 7'-0" x 1 3/4"	HM	2F	HM	B	CWS-3/A2.7	CWS-4/A2.7			
PASSAGE SET	NON-KEYED LOCKSET	142B	142	H.W. SET #32B	4'-0" x 7'-0" x 1 3/4"	SCW	NV	HM	A	CWS-1/A2.7	CWS-2/A2.7			
TOUCH LOCK	GM M		142C	H.W. SET #36	EXISTING	EXIST	EXIST					60 MIN	SEE REMARK #1	
TOUCH LOCK	GM M		146A	H.W. SET #36	EXISTING	EXIST	EXIST					60 MIN	SEE REMARK #1	
TOUCH LOCK	GM M		146B	H.W. SET #36	EXISTING	EXIST	EXIST					60 MIN	SEE REMARK #1	
OFFICE FUNCTION	GM M	K	147	H.W. SET #24B	EXISTING	EXIST	EXIST						SEE REMARK #1	
OFFICE FUNCTION	GM M	K	148	H.W. SET #24B	EXISTING	EXIST	EXIST						SEE REMARK #1	
OFFICE FUNCTION	GM M	K	149	H.W. SET #24B	EXISTING	EXIST	EXIST						SEE REMARK #1	
OFFICE FUNCTION	GM M	K	150	H.W. SET #24B	EXISTING	EXIST	EXIST						SEE REMARK #1	
OFFICE FUNCTION	GM M	K	151	H.W. SET #24B	EXISTING	EXIST	EXIST						SEE REMARK #1	
OFFICE FUNCTION	GM M	K	152	H.W. SET #24B	EXISTING	EXIST	EXIST						SEE REMARK #1	

- KEYING SCHEDULE NOTES:**
- CYLINDRICAL LOCKS ONLY. NO MORTISE LOCKS ARE TO BE USED.
 - GM, M, SM, K1 EMBOSSED NON-DUPLICATING KEY CORES.
 - INTERCHANGEABLE KEY CORES NOT APPLICABLE.
 - COORDINATE ALL KEYING WITH EXISTING MASTER KEY SYSTEM.

- GENERAL DOOR & DOOR FRAME SCHEDULE NOTES:**
- ALL GLAZING SHALL BE TEMPERED GLASS UNLESS NOTED OTHERWISE.
 - INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

- DOOR SCHEDULE ABBREVIATIONS:**
- ALUM = ALUMINUM
 - EXIST = EXISTING
 - HG = HALF GLASS
 - HM = HOLLOW METAL
 - SCW = SOLID CORE WOOD
 - NV = NARROW VISION LIGHT

- REMARKS:**
- EXISTING DOOR AND FRAME TO REMAIN. REMOVE EXISTING LOCKSET AND REPLACE WITH NEW LOCKSET. PROVIDE ADDITIONAL HARDWARE PER HARDWARE SET GUIDELINES IN SPECIFICATION SECTION 08710.
 - NOT USED.

KEY SCHEDULE ABBREVIATIONS:

- GM: GRAND MASTER OPENS ALL DOORS (PROVIDE 2 NON-DUPLICATING KEYS).
- M: INTERIOR MASTER (JANITORIAL) OPENS ALL DOORS EXCEPT MED. RECORDS 115 AND MED WASTE 106 (PROVIDE 2 NON-DUPLICATING KEYS). JANITORIAL USES, EMPLOYEE ENTRY.
- SM: SUB-MASTER SELECTED EMPLOYEES OPEN DOORS LISTED (PROVIDE 6 NON-DUPLICATING KEYS).
- K1: KEYED ALIKE, EXTERIOR DOORS ONLY (PROVIDE 6 NON-DUPLICATING KEYS).
- K: KEYED DIFFERENTLY, OPENS ASSIGNED OFFICE (PROVIDE 2 KEYS FOR EACH DOOR/OFFICE).

3 DOOR & DOOR FRAME SCHEDULE / KEYING SCHEDULE
A2.8 SCALE: N.T.S.

THE INTENT OF THESE DRAWINGS IS TO MATCH EXISTING FACILITIES INTERIOR COLOR SCHEME AND FINISH MATERIALS

COLOR SELECTION SCHEDULE	WALL FINISHES												FLOORING						COUNTERTOPS/ CASEWORK	
	PAINT				RIGID VINYL PANEL	FIBERGLASS WALL PANELS (FRP)	CORNER GUARDS	SHEET VINYL STANDARD	VINYL COMPOSITION TILE	VINYL COMPOSITION TILE	VINYL COMPOSITION TILE	WALL COVE BASE	WALK OFF CARPET	EPOXY	SOLID SURFACE [1]	PLASTIC LAMINATE				
	P1	P2	P3	P4	WP1	WP2	CG1	SV1	VCT1	VCT2	VCT3	RB1, RB2, RB3, CCI	MAT1	RF1	SS1	PL1				
Wall Color	Accent 1 Color	Door Frame Color	Ceiling Color	INPRO CORPORATION 1.800.214.7749 x2263 Order # 449986	KEMITE Kemeite Composite Company Kemeite Division Robert Moushy 781.626.5588 800.433.0080 Class A Rating REQUIRED	INPRO CORPORATION 1.800.214.7749 x2263 Order # 449986	COMPASS FLOORING Alto & Ehies jehmor@compassfloor.com 978.853.9007	ARMSTRONG WORLD INDUSTRIES, INC. Contact local Armstrong Distributor	ARMSTRONG WORLD INDUSTRIES, INC. Contact local Armstrong Distributor	ARMSTRONG WORLD INDUSTRIES, INC. Contact local Armstrong Distributor	JOHNSONITE Contact local Johnsonite Distributor	MATS, INC. Contact local Distributor	DUP-A-FLEX Steve Lerman office: 860.528.8838 cell: 860.870.4236 fax: 860.528.2888	LG Hi'Macs Volcanics	WILSONART Nurses Station Cabinetry @ Sinks in Treatment-Vertical Surface					
Benjamin Moore OC-14 Natural Creme Finish: Eggshell	Benjamin Moore 504 Finish: Eggshell	Benjamin Moore 2134-30 Iron Mountain Finish: Semi-Gloss	Benjamin Moore Ceiling White Finish: Flat	Chino 0258	83 Colonial White	Chino 0258	Alto Smooth Ethos 389-21 Golden Oak	Imperial Texture Standard Excelon 51929 Sandy Beach	Imperial Texture Standard Excelon 51858 Sandrift White	Imperial Texture Standard Excelon 51910 Classic Black	(RB1) 40- Black 8'-4" (RB2) 43 Burnt Umber 8'-4" (RB3) 262 Drizzle CG- 6"	Style: Berber Color: Charcoal #7	Shop Floor Medium Gray	Matin VG23	Color: TRD [2] Provide "Wood" Look Laminate to Match Door- Algoma Hardwoods, Inc. Sliced White Birch, RA-100					

- COUNTERTOP/ CASEWORK NOTES:**
- Solid Surface is to be used at all wet counter areas.
 - Provide a full line of Wilsonart wood look laminates as well as Algoma Hardwood, Inc., Color as specified, to Architect for selection.

2 COLOR SELECTION SCHEDULE
A2.8 SCALE: N.T.S.

ROOM FINISH, COLOR SELECTION AND DOOR SCHEDULES
SCALE: AS NOTED

LICENSED ARCHITECT
GUY T. LAROCQUE, P.E.
STATE OF MAINE

CWS
Architects

434 Cumberland Avenue
Portland, ME 04101
Phone: (207) 774-4441
Fax: (207) 774-4016
www.CW5arch.com

Dialysis Clinic Fit-Up:
SOUTHERN MAINE DIALYSIS
#1190
1600 CONGRESS STREET
PORTLAND, MAINE 04102

Drafted By:	CWS ARCH	
Checked By:	CWS - GTL	
Date Drawn:	03/06/12	
Project #:	CWS# 11418	
REV #	DATE	REVISION DESCRIPTION

A2.8
Sheet Number