

SECTION 01070

ABBREVIATIONS & DEFINITIONS

PART 1 - GENERAL

1.01 INTERPRETATIONS

- A. This section is not intended to cover all definitions which may be required, nor all the abbreviations which may be used on the Contract Documents.
- B. Questions regarding definition of terms, or meaning of abbreviations should be directed to the Architect.

1.02 DEFINITIONS

- A. The following definitions shall apply to the Specifications:
  - 1. The words "Furnish" or "Supply" means purchase and delivery of items or materials to the project site, including proper storage without installation.
  - 2. The word "Install" means applications, connection or erection of items or materials that have been furnished.
  - 3. The word "Provide" means both furnishing and supplying and installing of items or materials.
  - 4. The term "Work" as used herein refers to work at site of project and includes all labor and materials to be incorporated in the construction.
  - 5. The word "Concealed" means work within or behind various construction elements, or in crawl spaces or trenches, which is not exposed to view when the project is complete.
  - 6. The word "Exposed" means anything exposed to view when the project is complete, as opposed to being "concealed."

1.03 ABBREVIATIONS

- A. The following list of abbreviations shall apply to the Drawings and Specifications. This list is not all inclusive. Other abbreviations may exist on the drawings. If any questions arise regarding abbreviations, contact the Architect for interpretation.

A/B	Acid, Bicarb Tubing
ABV	Above
AC	Air Conditioning
ACT	Acoustical Tile
ADD	Addendum
ADJ	Adjacent
ADJT	Adjustable
AFF	Above Finished Floor
ALT	Alternate
ALUM	Aluminum
APPROX	Approximate

APX	Approximate
ARCH	Architect(ural)
AUTO	Automatic
BD	Board
BEL	Below
BET	Between
BIT	Bituminous
BK	Brick
BLK	Block
BLKG	Blocking
BOT	Bottom
BRG	Bearing
BRK	Brick
BSMT	Basement
CAB	Cabinet
CG	Corner Guard
CIPC	Cast-in-Place Concrete
CJ	Control Joint
CJT	Control Joint
CL	Clear
CLG	Ceiling
CMU	Concrete Masonry Unit
CO	Cased Opening
COL	Column
CONC	Concrete
CPT	Carpet
CRS	Course
CSC	Concealed Spline Ceiling
CT	Ceramic Tile
CTSK	Countersunk Screw
CW	City Water
DET	Detail
DI	Deionized Water
DIM	Dimension
DISP	Disposal
DISPEN	Dispenser
DO	Door Opening
DPL	Disposal
DPR	Dispenser
DR	Door
DW	Drywall
DWG	Drawing
DWR	Drawer
ELEC	Electrical
EMER	Emergency
EMR	Existing Material to Remove
EQ	Equal
EQUIP	Equipment
EXG	Existing
EXIST	Existing
EXT	Exterior

FCO		Floor Clean Out
FD		Floor Drain
FE		Fire Extinguisher
FEC		Fire Extinguisher Cabinet
FIN		Finish(ed)
FIXT		Fixture
FL	Floor	
FLR		Floor(ing)
FLUR		Fluorescent
FP		Fixed Panel
FS		Floor Sink
GA		Gage, Gauge
GL		Glass
GV		Galvanized
GWB		Gypsum Wall Board
H		High
HP		Handicapped
HR		Hour
HT		Height
HVAC		Heating-Ventilating-Air-Conditioning
HW		HW Hot Water
HWR		Hot Water Return
ID		Inside Diameter
INS		Insulate (d), (ion)
INT		Interior
IW		Indirect Waste
IWV		Indirect Waste Vent
JT		Joint
LAM		Laminate
LAV		Lavatory
LT		Light
MAS		Masonry
MAX		Maximum
MECH		Mechanical
MT		Metal
MIN		Minimum
MISC	Miscellaneous	
MO		Masonry Opening
MOV		Moveable
MRGB		Moisture Resistant Gypsum Wallboard
NIC		Not in Contract
NO		Number
NS		Nurses Station
NTS		Not to Scale
OA		Overall

OC	On Center
OF	Owner Furnished
OFI	Owner Furnished and Installed
OFIC	Owner Finished Installed by Contractor
OH	Opposite Hand
OPG	Opening
OPNG	Opening
PAT	Patient
PL	Plate
PLAM	Plastic Laminate
PLAS	Plaster
PLYWD	Plywood
PNL	Panel
PSTA	Patient Station
PTD	Paper Towel Dispenser
PTN	Partition
PTR	Paper Towel Dispenser
PVC	Poly. Vinyl Chloride
PWD	Plywood
R	Rubber
RA	Return Air
RB	Rubber Base
REF	Refrigerator
REFR	Refrigerator
REFRIG	Refrigerator
RM	Room
REMOV	Removable
RO	Reverse Osmosis (water)
RP	Removable Panel
SDS	Solution Delivery System
SHT	Sheet
SIM	Similar
SL	Sliding
SQ	Square
SR	Sheet Rubber
SST	Stainless Steel
ST	Steel
STA	Station
STD	Standard
STL	Steel
STR	Structural
STRUCT	Structural
STUC	Stucco
SUS	Suspended
THK	Thick(ness)
TKBD	Tackboard
TPD	Toilet Paper Dispenser
TYP	Typical
V	Vinyl
VCT	Vinyl Composition Tile
VERT	Vertical

VWC	Vinyl Wall Covering
WC	Water Closet
WCO	Wall Clean Out
WD	Wood
WDP	Wood Panel on Gypsum Wallboard
WIN	Window
WO	Window Opening

END OF SECTION