

**SECTION 01100**

**ALTERNATES**

**1.01 PROVISIONS INCLUDED**

- A. The conditions of the Contract and Division 1, General Requirements, apply to the work under this Section.

**1.02 DESCRIPTION OF WORK**

- A. Furnish all labor, materials and services necessary for the proper and complete execution of accepted alternates. The amount of alternate prices to be added to or deducted from the base bid shall be stated on the Bid Form and shall include the cost of any and all modifications made necessary by the Owner's acceptance of an alternate.
- B. State the amount to be added to or deducted from the base bid for each of the following alternates, if these alternates are added to the work of the Contract. The base bid shall not include the following listed alternates or work required to be performed in connection thereto.

**1.03 SCHEDULE OF ALTERNATES**

- A. Alternate Number 1: All work associated with the complete removal and replacement of the existing Nurse's Station. Includes but is not limited to demolition, concrete slab cutting and patching, architectural casework, electrical, etc. Reference removals plans, new work plans and A1.3 for additional information.
- B. Alternate Number 2: The complete removal and replacement of the existing VCT floor finishes within Corridor 129. Reference removals plans and new work plans for additional information.
- C. Alternate Number 3: The complete replacement of the existing VCT with Altro Maxis sheet vinyl within Treatment Room 118. This would be accomplished on a per phase basis and would extend throughout the space.
- A. Alternate Number 4: The complete replacement of the existing VCT with VCT within Treatment Room 118. This would be accomplished on a per phase basis and would extend throughout the space

**END OF SECTION**