

SECTION 03530
CONCRETE FLOOR TOPPING

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:
 - 1. Emery-aggregate concrete floor topping.
- B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:
 - 1. Section 03300 - CAST-IN-PLACE CONCRETE for concrete slab construction and finish.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for concrete floor toppings.

1.3 QUALITY ASSURANCE

- A. Installer: Installer shall be certified by the product manufacturer or demonstrate 3 years previous experience installing product.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials in original packages and containers, with seals unbroken, bearing manufacturer's labels indicating brand name and directions for storage, mixing with other components, and application.
- B. Store materials to comply with manufacturer's written instructions to prevent deterioration from moisture or other detrimental effects.

1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Comply with manufacturer's written instructions for substrate temperature and moisture content, ambient temperature and humidity, ventilation, and other conditions affecting concrete floor topping performance.
 - 1. Place concrete floor topping only when ambient temperature and temperature of base slabs are between 50 and 86 deg F.
- B. Close areas to traffic during topping application and, after application, for time period recommended in writing by manufacturer.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Emery-Aggregate Concrete Floor Topping:
 - a. Anti-Hydro International, Inc.; A-H Emery A-1 Premix.
 - b. Dayton Superior Corporation; Emery Tuff Top.
 - c. Emeri-Crete, Inc.; Emeri-Crete.
 - d. L&M Construction Chemicals, Inc.; Emerytop 400.
 - e. Metalcrete Industries; Met-Top E.
 - f. Vexcon Chemicals, Inc.; Emeri-Crete SH.

2.2 CONCRETE FLOOR TOPPINGS

- A. Emery-Aggregate Concrete Floor Topping: Factory-prepared and dry-packaged mixture of graded, crushed emery aggregate containing not less than 50 percent aluminum oxide, not less than 24 percent ferric oxide, and not more than 8 percent silica; portland cement or blended hydraulic cement; plasticizers; and other admixtures to which only water needs to be added at Project site.
 - 1. Compressive Strength (28 Days): 7000 psi; ASTM C 109/C 109M.

2.3 CURING MATERIALS

- A. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. when dry.
- B. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.

- C. Water: Potable.
- D. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B, 25 percent solids content, minimum.

2.4 RELATED MATERIALS

- A. Semirigid Joint Filler: Two-component, semirigid, 100 percent solids, epoxy resin with a semi-rigid Type A Shore durometer hardness of 80 per ASTM D 2240.
- B. Joint-Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber.
- C. Portland Cement: ASTM C 150, Type I or II.
- D. Sand: ASTM C 404, fine aggregate passing No. 16 sieve.
- E. Water: Potable.
- F. Acrylic-Bonding Agent: ASTM C 1059, Type II, non-redispersible, acrylic emulsion or styrene butadiene.

2.5 MIXING

- A. Bonding Slurry: Mix portland cement with water to a thick paint consistency and as recommended by manufacturer of floor topping.
- B. Floor Topping: Mix concrete floor topping materials and water in appropriate drum-type batch machine mixer or truck mixer according to manufacturer's written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for conditions affecting performance of concrete floor topping.
- B. Verify that base concrete slabs comply with scratch finish requirements specified in Section 03300 - CAST-IN-PLACE CONCRETE.
- C. Verify that base slabs are visibly dry and free of moisture. Test for capillary moisture by the plastic sheet method according to ASTM D 4263.
- D. Proceed with application only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Existing Concrete: Remove existing surface treatments and deteriorated and unsound concrete. Mechanically abrade base slabs to produce a heavily scarified surface profile with an amplitude of 1/4 inch.
 - 1. Prepare and clean existing base slabs according to concrete floor topping manufacturer's written instructions. Fill voids, cracks, and cavities in base slabs.
 - 2. Mechanically remove contaminants from existing concrete that might impair bond of floor topping.
 - 3. Saw cut contraction and construction joints in existing concrete to a depth of 1/2 inch and fill with semirigid joint filler.
- B. Install joint-filler strips where topping abuts vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.
 - 1. Extend joint-filler strips full width and depth of joint, terminating flush with topping surface, unless otherwise indicated.
 - 2. Terminate full-width, joint-filler strips 1/2 inch below topping surface where joint sealants, specified in Section 07920 - JOINT SEALANTS, are indicated.
 - 3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.

3.3 FLOOR TOPPING APPLICATION

- A. Start floor topping application in presence of manufacturer's technical representative.
- B. Monolithic Floor Topping: After textured-float finish is applied to fresh concrete of base slabs, place concrete floor topping while concrete is still plastic.
- C. Deferred Floor Topping: Within 72 hours of placing base slabs, mix and scrub bonding slurry into dampened concrete to a thickness of 1/16 to 1/8 inch, without puddling. Place floor topping while slurry is still tacky.
- D. Place concrete floor topping continuously in a single layer, tamping and consolidating to achieve tight contact with bonding surface. Do not permit cold joints or seams to develop within pour strip.
 - 1. Screed surface with a straightedge and strike off to correct elevations.
 - 2. Slope surfaces uniformly where indicated.
 - 3. Begin initial floating using bull floats to form a uniform and open-textured surface plane free of humps or hollows.
- E. Finishing: Consolidate surface with power-driven floats as soon as concrete floor topping can support equipment and operator. Re-straighten, cut down high spots, and fill low spots. Repeat float passes and re-straightening until concrete floor topping surface has a uniform, smooth, granular texture.

1. Hard Trowel Finish: After floating surface, apply first trowel finish and consolidate concrete floor topping by power-driven trowel without allowing blisters to develop. Continue troweling passes and re-straighten until surface is smooth and uniform in texture.
 - a. Finish and measure surface so gap at any point between surface and an unlevelled freestanding 10-foot-long straightedge, resting on 2 high spots and placed anywhere on the surface, does not exceed 1/8" inch.
- F. Construction Joints: Construct joints true to line with faces perpendicular to surface plane of concrete floor topping, at locations indicated or as approved by Architect.
- G. Contraction Joints: Form weakened-plane contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch-wide joints into concrete floor topping when cutting action will not tear, abrade, or otherwise damage surface and before random contraction cracks develop.
 1. Form joints in concrete floor topping over contraction joints in base slabs, unless otherwise indicated.
 2. Construct contraction joints for a depth equal to one-half of concrete floor topping thickness, but not less than 1/2 inch deep.

3.4 PROTECTING AND CURING

- A. General: Protect freshly placed concrete floor topping from premature drying and excessive cold or hot temperatures.
- B. Evaporation Retarder: Apply evaporation retarder to concrete floor topping surfaces in hot, dry, or windy conditions before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying floor topping, but before float finishing.
- C. Begin curing immediately after finishing concrete floor topping. Cure by one or a combination of the following methods, according to concrete floor topping manufacturer's written instructions:
 1. Curing Compound: Apply uniformly in two coats in continuous operations by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.

3.5 JOINT FILLING

- A. Prepare and clean contraction joints and install semi-rigid joint filler, according to manufacturer's written instructions, once topping has fully cured.

- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joint clean and dry.
- C. Install semi-rigid joint filler full depth of contraction joints. Overfill joint and trim semi-rigid joint filler flush with top of joint after hardening.

3.6 REPAIRS

- A. Defective Topping: Repair and patch defective concrete floor topping areas, including areas that have not bonded to concrete substrate.

3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Testing Services: Testing and inspecting of completed applications of concrete floor toppings shall take place in successive stages, in areas of extent and using methods as follows:
 - 1. Sample Sets: At point of placement, a set of 3 molded-cube samples shall be taken from the topping mix for the first 1000 sq. ft., plus 1 set of samples for each subsequent 5000 sq. ft. of topping, or fraction thereof, but not less than 6 samples for each day's placement. Samples shall be tested according to ASTM C 109/C 109M for compliance with compressive-strength requirements.
 - 2. Concrete floor topping shall be tested for delamination by dragging a steel chain over the surface.
 - 3. Concrete floor topping shall be tested for compliance with surface flatness and levelness tolerances.
- C. Remove and replace applications of concrete floor topping where test results indicate that it does not comply with specified requirements.
- D. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

END OF SECTION