

SECTION 10155
TOILET COMPARTMENTS

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:
 - 1. Floor-mounted overhead-braced toilet partitions and wall-hung urinal screens fabricated from baked-enamel coated metal.
- B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:
 - 1. Section 10810 - TOILET ACCESSORIES for partition mounted accessories.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
 - 1. Show locations of cutouts for compartment-mounted toilet accessories.
- C. Samples for Verification: Of each type of color and finish required for units, prepared on 6-inch-square samples of same thickness and material indicated for Work.

1.3 PROJECT CONDITIONS

- A. Field Measurements: Verify actual locations of walls, columns, ceilings, and other construction contiguous with toilet compartments by field measurements before fabrication and indicate measurements on Shop Drawings.
 - 1. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating toilet compartments without field measurements. Coordinate wall, floor, ceilings, and other contiguous construction to ensure that actual dimensions correspond to established dimensions.

PART 2 - PRODUCTS

2.1 METAL TOILET PARTITIONS (Floor-supported, overhead braced)

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. American Sanitary Partition Corporation.
 2. Global Steel Products Corp.
 3. Knickerbocker Partitions Corp.
- B. Baked-Enamel Units: Facing sheets and closures fabricated from ASTM A 653/A 653M (hot-dip galvanized or galvanized), commercial steel sheet for exposed applications, that is mill phosphatized, and selected for smoothness.
1. Facing Sheet Thicknesses: Minimum base-metal (uncoated) thicknesses as follows:
 - a. Pilasters, Braced at Both Ends: Manufacturer's standard thickness, but not less than 0.0329 inch.
 - b. Panels: Manufacturer's standard thickness, but not less than 0.0269 inch.
 - c. Doors: Manufacturer's standard thickness, but not less than 0.0269 inch.
 - d. Wall-Hung Urinal Screens: Manufacturer's standard thickness, but not less than 0.0269 inch.
 2. Finish: Manufacturer's standard pigmented, organic coating, including thermosetting, electrostatically applied, and powder coatings. Provide coating system that complies with coating manufacturer's written instructions for pretreatment, application, baking, and minimum dry film thickness.
 - a. Color: One color in each room as selected by Architect from manufacturer's full range of colors.
- C. Door, Panel, and Pilaster Construction: Seamless, metal facing sheets are pressure laminated to core material. Units have continuous, interlocking molding strip or lapped and formed edge closures. Exposed surfaces are free of pitting, seam marks, roller marks, stains, discolorations, telegraphing of core material, or other imperfections. Corners are sealed by welding or clips. Exposed welds are ground smooth.
1. Core Material: Manufacturer's standard sound-deadening honeycomb of resin-impregnated kraft paper in thickness required to provide finished thickness of 1 inch for doors and panels and 1-1/4 inches for pilasters.
 2. Grab-Bar Reinforcement: Provide concealed internal reinforcement for grab bars mounted on units.
 3. Tapping Reinforcement: Provide concealed reinforcement for tapping (threading) at locations where machine screws are used for attaching items to units.

4. Urinal-Screen Construction: Similar to panels, with integral full-height flanges for wall attachment, and maximum 1-1/4 inches thick.
- D. Pilaster Shoes and Sleeves: Stainless steel, ASTM A 666, Type 302 or 304, not less than 0.0312 inch specified thickness and 3 inches high, finished to match hardware.
- E. Brackets (Fittings):
 1. Full-Height (Continuous) Type: Manufacturer's standard design; stainless steel or aluminum.

2.2 ACCESSORIES

- A. Hardware and Accessories: Manufacturer's standard design, heavy-duty operating hardware and accessories.
- B. Overhead Bracing: Manufacturer's standard continuous, extruded-aluminum head rail with antigrip profile and in manufacturer's standard finish.
- C. Anchorages and Fasteners: Manufacturer's standard exposed fasteners of stainless steel or chrome-plated steel or brass, finished to match hardware, with theft-resistant-type heads. Provide sex-type bolts for through-bolt applications. For concealed anchors, use hot-dip galvanized or other rust-resistant, protective-coated steel.

2.3 FABRICATION

- A. Overhead-Braced Units: Provide manufacturer's standard corrosion-resistant supports, leveling mechanism, fasteners, and anchors at pilasters to suit floor conditions. Make provisions for setting and securing continuous head rail at top of each pilaster. Provide shoes at pilasters to conceal supports and leveling mechanism.
- B. Doors: Unless otherwise indicated, provide 24-inch-wide in-swinging doors for standard toilet compartments and 36-inch-wide out-swinging doors with a minimum 32-inch-wide clear opening for compartments indicated to be accessible to people with disabilities.
 1. Hinges: Manufacturer's standard self-closing type that can be adjusted to hold doors open at any angle up to 90 degrees.
 2. Latch and Keeper: Manufacturer's standard latch unit designed for emergency access and with combination rubber-faced door strike and keeper. Provide units that comply with accessibility requirements of authorities having jurisdiction at compartments indicated to be accessible to people with disabilities.
 3. Coat Hook: Manufacturer's standard combination hooks and rubber-tipped bumper, sized to prevent door from hitting compartment-mounted accessories.
 4. Door Bumper: Manufacturer's standard rubber-tipped bumper at out-swinging doors.

5. Door Pull: Manufacturer's standard unit at out-swinging doors that complies with accessibility requirements of authorities having jurisdiction. Provide units on both sides of doors at compartments indicated to be accessible to people with disabilities.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Comply with manufacturer's written installation instructions. Install units rigid, straight, level, and plumb. Secure units in position with manufacturer's recommended anchoring devices.
 1. Maximum Clearances:
 - a. Pilasters and Panels: 1/2 inch.
 - b. Panels and Walls: 1 inch.
 2. Stirrup Brackets: Secure panels to walls and to pilasters with not less than two brackets near top and bottom of panel.
 - a. Locate wall brackets so holes for wall anchors occur in masonry or tile joints.
 - b. Align brackets at pilasters with brackets at walls.
- B. Overhead-Braced Units: Secure pilasters to floor and level, plumb, and tighten. Secure continuous head rail to each pilaster with not less than two fasteners. Hang doors to align tops of doors with tops of panels and adjust so tops of doors are parallel with overhead brace when doors are in closed position.
- C. Wall-Hung Urinal Screens: Attach with anchoring devices to suit supporting structure. Set units level and plumb and to resist lateral impact.

3.2 ADJUSTING

- A. Hardware Adjustment: Adjust and lubricate hardware according to manufacturer's written instructions for proper operation. Set hinges on in-swinging doors to hold doors open approximately 30 degrees from closed position when unlatched. Set hinges on out-swinging doors and doors in entrance screens to return doors to fully closed position.

END OF SECTION