

SECTION 10810
TOILET ACCESSORIES

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:
 - 1. Toilet accessories as scheduled on the Drawings. Coordinate with Owner for accessories provided by Owner.
- B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:
 - 1. Section 06100 - ROUGH CARPENTRY for blocking.
 - 2. Division 15 - PLUMBING.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated. Include the following:
 - 1. Construction details and dimensions.
 - 2. Anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
 - 3. Material and finish descriptions.
 - 4. Features that will be included for Project.
 - 5. Manufacturer's warranty.
- B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.
 - 1. Identify locations using room designations indicated on Drawings.
 - 2. Identify products using designations indicated on Drawings.
- C. Maintenance Data: For toilet accessories to include in maintenance manuals.

1.3 QUALITY ASSURANCE

- A. Source Limitations: For products listed together in the same articles in Part 2, provide products of same manufacturer unless otherwise approved by Architect.

1.4 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. American Specialties, Inc.
 - 2. Bobrick Washroom Equipment, Inc.

2.2 MATERIALS

- A. Anchors and Fasteners:
 - 1. Provide anchors and fasteners capable of developing a retaining force commensurate with the strength of the accessory to be mounted, and well suited for use with the supporting construction.
 - 2. Where exposed fasteners are permitted, provide oval head fasteners with finish matching the accessory.
- B. Provide stainless steel with satin finish on all items of this Section.
- C. Acceptable Manufacturers:
 - 1. Provide all items from a single manufacturer.
 - 2. Where indicated on the Drawings or otherwise required, provide the following items or equal products of another manufacturer approved in advance by the Owner.

2.2.1 MATERIALS

ITEM #	DESCRIPTION	BOBRICK	AMERICAN SPECIALITES	CLINIC LOCATIONS
1	Toilet Tissue Dispenser (Recessed)	B-667	7402	1,2,7
2	Toilet Tissue Dispenser (Surface Mounted)	B-6857	0710	*
3	Surface Mounted Paper Towel Dispenser	B-262	0210	1,2,4,7,8,9*,10*,11,13,15*,17*,19*
4	Surface Mounted Paper Towel Dispenser (at half walls)*	B-26212	0215	13*
5	Countertop Paper Towel Dispenser	B-526	1002	13*
6	24 x 36 Mirror w/Stainless Steel Frame	B-290-2436	0620-2436	1,2,3,5,7,17*
7	24 x 30 Mirror W/Stainless Steel Frame	B-290-2430	0620-2430	4
8	24 x 60 Mirror w/Stainless Steel Frame	B-290-2460	0620-2460	16
9	Wall Mounted Grab Bar	B-5806.99x42x36	3100-42,36	1,2,7,12 (42")
10	Grab Bar Anchors	B-2562 Series	N/A	1,2,7,12
11	Mop Holder	B-223x36	8215-4	14

*As indicated on drawings

ITEM #	DESCRIPTION	GALLERY SPECIALTY HARDWARE LTD. 1-800-267-1236	FINISH NOTE	
1	Clothing Hook - Large	308A	US10B Finish	3,4,5,6,7,18
2	Clothing Hook - Small	311	US10B Finish	1,2

CLINIC LOCATIONS

ROOM NO.	ROOM DESCRIPTION
1	Patient Toilets
2	Visitor Toilets
3	CAPD Room
4	Doctor/Exam and/or Exam Room
5	Home Hemo Training Room
6	All Offices & Reception
7	Staff Toilets
8	Lounge
9	Vending Area
10	Isolation Room
11	Soiled Utility Room
12	Electronic Scale
13	Med/Lab Prep Areas & Prep Sinks
14	Janitor's Closet
15	Tech Repair Area
16	Changing Room
17	Training Room
18	Inservice Coordinator
19	Clean Utility

2.3 FABRICATION

- A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.
- B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to the Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- B. Grab Bars: Install to withstand a downward load of at least 250 lbf, when tested according to method in ASTM F 446.

3.2 ADJUSTING AND CLEANING

- A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written recommendations.

END OF SECTION