

**SECTION 11461
PREFABRICATED CABINETS**

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Work included: Provide prefabricated cabinets where shown on the Drawings, as specified herein, and as needed for a complete and proper installation.
- B. Related work: The following items are not included in this section and will be performed under the designated Sections:
 - 1. Section 06402 – INTERIOR ARCHITECTURAL WOODWORK for countertop, sidesplash and backsplash installation.
 - 2. Section 09260 – GYPSUM BOARD ASSEMBLIES for finished wallboard interface.

1.2 SUBMITTALS

- A. Comply with pertinent provisions of Section 01340.
- B. Product data: Within 20 calendar days after the Contractor has received the Owner's Notice to Proceed, submit sufficient technical data to enable interface of the work of this Section with the work of mechanical and electrical trades.
- C. Submit a plan showing cabinet layout and sizes.
- D. Submit manufacturer's catalog cut sheets.

1.3 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.4 PRODUCT HANDLING

- A. Comply with pertinent provisions of Section 01640.

PART 2 - PRODUCTS

2.1 PREFABRICATED CABINETS

- C. Acceptable Manufacturers:

NOTE: Cabinetry can be purchased with a discount off of the manufacturers list price through the Fresenius Medical Care, National account program, by identifying this as a Fresenius project.

1. Ultracraft Cabinetry, (Entree' line), Better Cabinet Distributors, Inc.
100 Pleasant Street, Dracut, MA 01836. Tel: 800 766-8771 / 978 957-9316
Contact: Customer service – Erin Lynch or Robin Pollack

Pricing: East Coast .28 landed east of the Mississippi river
Central states .32 landed Mississippi river to the Rocky Mountains
West Coast .30 landed west of the Rocky Mountains
Product lead-time is 4 weeks or less.

2. Dwyer Kitchens
320 West Ohio Street, Suite 610
Chicago, IL 60610
www.dwyerkitchens.com

Pricing: Submit cabinet list for price quote.

Contact: Suzanne M. Buelow, VP of Healthcare Sales

Tel: 1-800-822-0092 x 308

Fax: 630-741-7974

Sbuelow@dwyerkitchens.com

Lead Time: 4 – 6 weeks after receipt of P.O. and approved credit or payment agreement.

D. Construction

1. Doors and Drawer Heads: Shall be 5/8" minimum thickness, 45 lb. density furniture grade particle board, covered with low pressure plastic laminate on both faces. Band edges with .018" thick vinyl edge banding tape. Doors and drawer heads shall be a full overlay design.
2. Drawers: Provide rigid 5/8" melamine drawer box, glued and dowelled with fully captured bottom.
3. Drawer Guides: Epoxy coated, self-closing, 75# drawer glides with positive stop in the fully extended position.
4. Cabinet Construction: Cabinet sides, bottoms, stretchers and hanging rails shall be 5/8" thick melamine. Cabinet backs shall be fitted or captured with a minimum 1/4" thickness.
5. Hinges: Fully concealed, self closing, clip-on, six way adjustable, 107 degree steel hinge with lifetime warrantee.

6. Shelves: Provide 5/8” minimum thickness melamine board. Provide roll-out trays in all standard base cabinets.
7. Provide toe kick with all base cabinets.
8. Finish: All interior surfaces shall be melamine finish.
9. Colors: Shall be white.
10. Pulls: Provide white vinyl coated wire pulls for all operating drawer and panel fronts.
11. Locks: Provide keyed alike locks at locations indicated on the drawings and as follows: Manufacturer:
 - National Cabinet Lock
 - Lock: C8054 5 disc tumbler cam lock
 - Strike: C2002

PART 3 - EXECUTION

3.1 DESCRIPTION

- A. Installation of cabinets, including the trimming of base cabinets for handicapped accessibility, provided in this section shall be as specified in INTERIOR ARCHITECTURAL WOODWORK - Section 06202.

END OF SECTION