

SECTION 16910

TEMPERATURE CONTROLS

PART 1 - GENERAL

1.01 WORK INCLUDED

- A. The furnishings of the temperature controls are, in general, not within the scope of Division 16. However, wiring and connecting of all equipment operator controls and indication equipment provided and set in place by others that is not performed under other Division of Work shall be a part of this Division of Work.
- B. Refer to Division 15 of these Drawings and Specifications for information as to the scope of this work.

1.02 REFERENCE DOCUMENTS

- A. The Special Provisions for Electrical Work are hereby made a part of this Section of the Work. Refer to Section 16010.
- B. Refer to Division 15, "15550 Controls" for work and materials.
- C. Refer to Sections 16100 Series for materials to be furnished and installed.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Raceways as specified in Section 16110 and Section 16111, Conduit.
- B. Wire and cable as specified in Section 16120.
- C. Pull boxes, Junction Boxes, Cabinets, and Outlet Boxes as specified in Sections 16131, 16133 and 16134.
- D. Hangers and Supports as specified in Section 16190.

PART 3 - EXECUTION

3.01 INSTALLATION

- A. Furnish and install all conduit, wire, boxes and common wiring materials necessary for the work unless specifically excluded elsewhere in the Specifications or on the Drawings.
- B. The Owner or other Contractors or other Divisions of Work will furnish the exact locations or equipment, and also all instructions and wiring diagrams necessary to select the materials required to install this equipment properly.

END OF SECTION