Southern Maine Dialysis #1190 — **9/4/2007**

Portland, Maine

Room Finish & Color Schedule

Room No.	Room Name	Flooring Color	Base Color	Wall Colors - Sherwim Williams Paint Colors				Paint Color	Paint Color	Paint System	Wall Covering		Corner Guards	Chair Rails	FRP	Laminate	Solid Surfacing	Wood Trim	Floor Mat	CEILING		REMARKS
			Johnsonite Rubber or as otherwise indicated	North	East	South	West	Door Frames	Dialysis Panel Fronts	Ref. Spec. 09900	Wolf Gordon G4803562	Wall Carpet	Pawling	Pawling		(Wilsonart Chemsurf required @ Dialysis Counters only)	Wilsonart Gibraltar		Mats Inc.	MATERIAL	CEILING HEIGHT	
100	**SDS / Granuflo**																					
	Field / Main Body Color	Dur-A-Flex Shop Floor - Medium Gray	Integral cove base			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss		P-2 / P-4			#301 Linen White		Kemlite #85 White							7
102	**Storage**																					
	Field / Main Body Color					SW 1003 First Star - Eggshell		SW 1003 First Star - Semi-Gloss		P-2 / P-4												
105	**Storage**																					
	Field / Main Body Color			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell			P-2 / P-4												
115	**Janitor's**																					
	Field / Main Body Color			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss		P-2 / P-4					Kemlite #85 White							5, 7, 11
116	**Soiled Utility**																					
	Field / Main Body Color			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss		P-2 / P-4					Kemlite #85 White							5, 7, 11
118	**Treatment Room - XVCT**																					
Base Bid	Field Color	Armstrong 51905 - Hazelnut	Johnsonite - #55 Silver Grey	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss	SW 6086 Sand Dune - Semi-Gloss	P-2 / P-4			#301 Linen White			4557-60 Dakota Ridge	Fawn Mirage D309MG	Clear Satin Finish		ACT-1		1, 5
	Accent Color	Armstrong 51908 - Pewter																				
118	**Treatment Room - VCT**																					
Alt. #4	Field Color	Armstrong 57202 Canvas Beige	Johnsonite - #55 Silver Grey	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss	SW 6086 Sand Dune - Semi-Gloss	P-2 / P-4			#301 Linen White			4557-60 Dakota Ridge	Astral Spectra 9170ST	Clear Satin Finish		ACT-1		1, 5
118	**Treatment - SV**																					
Alt. #3	Field Color	Altro Maxis Epic MX125212	Integral Cove Base	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss	SW 6086 Sand Dune - Semi-Gloss	P-2 / P-4			#301 Linen White			4557-60 Dakota Ridge	Astral Spectra 9170ST	Clear Satin Finish		ACT-1		1, 5
	Weldrod	105																				
	Mastic 100	1																				
	Cove Base Top Cap		Johnsonite - #55 Silver Grey																			
119	**Reception**																					
	Field / Main Body Color																Hi Macs G09 Black Sand	Clear Satin Finish				
121	**Coats/Wheel Chairs**																					
	Field / Main Body Color	Altro Smooth Ethos - Golden Oak 389-21	Johnsonite - #40 Black								Caribe Antique White #54 W WC - #CBE5-1100	Source One Waterbrush AWB-05 Basilica	#301 Linen White					Clear Satin Finish				2, 3, 4, 10
129	**Corridor**																					
Base Bid	Field / Main Body Color	Altro Smooth Ethos - Golden Oak 389-21	Johnsonite - #40 Black	SW 1116 Vellum - Eggshell	SW 1116 Vellum - Eggshell	SW 1116 Vellum - Eggshell	SW 1116 Vellum - Eggshell	SW6258 Tricorn Black - Semi-Gloss		P-1 / P-4			#301 Linen White	WGG-4 Mission White	Kemlite #70 Beige			Clear Satin Finish				6, 10
129	**Corridor**																					
Alt. #2	Field Color	Armstrong 51929 Sandy Beach	Johnsonite - #40 Black	SW 1116 Vellum - Eggshell	SW 1116 Vellum - Eggshell	SW 1116 Vellum - Eggshell	SW 1116 Vellum - Eggshell	SW6258 Tricorn Black - Semi-Gloss		P-1 / P-4			#301 Linen White	WGG-4 Mission White	Kemlite #70 Beige			Clear Satin Finish				6, 10
	Accent Color	Armstrong 51858 Sandrift White																				
	Highlight Color	Armstrong 51910 Classic Black																				
130	**Waiting**																					
	Field / Main Body Color	Altro Smooth Ethos - Golden Oak 389-21	Johnsonite - #40 Black					SW6258 Tricorn Black - Semi-Gloss		P-4	Caribe Antique White #54 W WC - #CBE5-1100	Source One Waterbrush AWB-05 Basilica	#301 Linen White					Clear Satin Finish				2, 3, 4, 8, 10
131	**Vestibule**																					
	Field Color			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell			P-1									Berber - Charcoal #7			5
132	**Home Hemo Room**																					
	Field Color			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss		P-2 / P-4												8
133	**Home Hemo Room**																					
	Field Color			SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss		P-2 / P-4												8
136	**Wiring Closet**																					
	Field / Main Body Color	Armstrong 51905 - Hazelnut	Johnsonite - #55 Silver Grey	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Eggshell	SW 1003 First Star - Semi-Gloss		P-1 / P-4										ACT-1	9'-0"	
137	**Water Treatment**																					
	Field / Main Body Color	Floor - Medium Gray	Integral Cove Base		Tricorn Black - Eggshell	Tricorn Black - Eggshell	Tricorn Black - Eggshell			P-2 / P-4			#301 Linen White									9

Room Finish & Color Schedule Remarks

1	Existing suspended ceiling grid to remain. Repair, and prepare for new paint finishes. Provide paint applications to existing grid. Utilize paint system P-7. Provide new acoustical tile throughout space.
2	Provide continuous hardwood chair rail with paint system P-6 finishes.
3	Provide vinyl wall coverings above chairrail to underside of ceiling.
4	Provide continuous wall carpet from finish floor to chairrail/vinyl wall covering.
5	Patch and repair gab surfaces. Provide paint applications entire body of wall.
6	Provide 4'-0" FRP wainscot and vinyl chairrail as indicated within the floor plans.
7	Provide 8'-0" FRP finishes as indicate within the floor plans - ref. A1.1.
8	Provide new paint finishes to existing door frame. Corridor side of frame only.
9	Provide plywood surfacing to height indicated within the floor plans. Paint finish utilizing paint system P-5.
10	Reference miscellaneous floor plans and drawings A1.3 and A1.4 for limits of new sheet vinyl.
11	Provide paint finishes to existing GWB ceiling assembly. Utilize paint system P-2.