


SLAB REMOVALS NOTES:

- IT IS NOT THE INTENT OF THESE SLAB REMOVAL DRAWINGS TO COMPLETELY IDENTIFY ALL SLAB REMOVALS. THE LIMITS INDICATED ARE INTENDED TO BE UTILIZED AS A BASIS OF INTENT BUT WILL REQUIRE FURTHER FILED REVIEW. THESE LIMITS ARE BASED UPON OTHER DRAWINGS THAT ARE UNDERSTOOD TO REFLECT ACTUAL EXISTING CONDITIONS DRAWINGS. THESE DRAWINGS ARE INCLUDED WITHIN THIS CONSTRUCTION DOCUMENTATION PACKAGE AND ARE TO BE UTILIZED FOR REFERENCE PURPOSES. ACTUAL UNDER-SLAB CONDITIONS MAY VARY AND WILL NEED TO BE VERIFIED AS THE WORK IS UNDERTAKEN.
- ALL SLAB REMOVALS SHALL BE COORDINATED WITH THE PLUMBING DRAWINGS PRIOR TO SLAB REMOVAL.
- UPON COMPLETING ALL UNDER-SLAB PLUMBING INSTALLATIONS THE CONTRACTOR SHALL PATCH AND REPAIR THE EXISTING VAPOR BARRIER SEALING TIGHT TO EXISTING PERIMETER. CONCRETE FILL/PATCH NEW OPENING TO ALIGN FLUSH TO ADJACENT SLAB EDGE. PROVIDE LEVELING COMPOUND AROUND ALL OPENINGS AS REQUIRED TO HIDE ROUGH JOINTS THAT WILL TELESTRATE THROUGH NEW FLOOR FINISHES.

SLAB REMOVALS LEGEND:

 = EXTENT OF CONCRETE SLAB REMOVALS AS REQUIRED TO ALLOW FOR NEW PLUMBING INSTALLATION - REFERENCE PLUMBING DOCUMENTS FOR MORE INFORMATION.