

## SECTION 06200

## FINISH CARPENTRY

1 PART 1 GENERAL

## 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

## 1.2 SUMMARY

- A. Finish carpentry items, other than shop prefabricated casework; hardware and attachment accessories.

## 1.3 QUALITY ASSURANCE

- A. Perform work in accordance with AWI Quality Standards, Custom Grade.

2 PART 2 PRODUCTS

## 2.1 LUMBER MATERIALS

- A. Softwood Lumber: N/A
- B. Hardwood Lumber: Graded in accordance with AWI Custom; Natural Birch species, plain sawn, maximum moisture content of 11 percent; of quality suitable for transparent finish.

## 2.2 ACCESSORIES

- A. Fasteners: Size and type to suit application; hot dipped galvanized steel for exterior, high humidity and treated wood locations, plain finish elsewhere.
- B. Primer: Alkyd primer sealer type.

## 2.3 FABRICATION

- A. Fabricate to AWI Custom standards.

3 PART 3 EXECUTION

## 3.1 EXAMINATION AND PREPARATION

- A. Prime paint back surfaces of items or assemblies, before installation. Where transparent finish is scheduled, back prime with spar varnish.

### 3.2 INSTALLATION

- A. Install work in accordance with AWI Custom quality standard.
- B. Set and secure materials and components in place, plumb and level.
- C. Install trim by nails. .

### 3.3 PREPARATION FOR FINISH

- A. Sand work smooth and set exposed fasteners. Apply wood filler in exposed fastener indentations.
- B. Site Finishing: Refer to Section 09900.

### 3.4 SCHEDULE

- A. Interior:
  - 1. Moldings, Chairrail, Bases, Casings, and Miscellaneous Trim: Birch, prepare for clear, satin finish polyurethane finishes.
  - 2. Wall Caps: Birch, prepare for clear, satin finish polyurethane finishes.
  - 3. Coat Shelves: Birch veneer plywood, prepare for clear, satin finish polyurethane finishes.

END OF SECTION