

SECTION 10190

CUBICLE CURTAINS AND TRACKS

1 PART 1 GENERAL

1.1 SUMMARY

- A. Work included: Provide cubicle curtains and tracks where indicated on the Drawings, as specified herein, and as needed for a complete and proper installation.
- B. Related work:
 - a. Documents affecting work of this Section include, but are not necessarily limited to Sections in Division 1, and Section 09510 Acoustical Ceilings of these Specifications.

1.2 SUBMITTALS

- A. Comply with pertinent provisions of Section 01340. Shop drawings, product data and samples.
- B. Product data: Within 20 calendar days after the Contractor has received Owner's Notice to Proceed, submit:
 - 1. Materials list of items proposed to be provided under this Section.
 - b. Shop Drawings showing proposed method of installation, anchoring, and interface between the work of this Section and the work of adjacent trades.
 - c. Manufacturer's recommended installation procedures.

1.3 QUALITY ASSURANCE

- A. Use adequate numbers of skilled personnel who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.4 PRODUCT HANDLING

- A. Deliver materials in unopened factory packaging to the jobsite.
- B. Inspect materials at delivery to assure that specified products have been received.
- C. Store in original packaging in a climate controlled location away from direct sunlight.

2 PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. General Cubicle Company, Inc., P.O. Box 9, Telford, PA 18969. Phone: 215-723-8931, Fax: 215-723-4698.
www.generalcubicle.com

- B. Imperial Fastener Company, 1400 S.W. 8th Street, Pompano Beach, Florida 33069. Phone: 954-782-7130, Fax: 954-782-0089.
www.imperialfastener.com
- C. BEI Healthcare Interiors, 720 Middle Ground Blvd., Newport News, VA 23606, Phone: 1.800.227.6602, Fax: 757.873.0212
www.beionline.com

2.2 TRACK COMPONENTS

- A. Cubicle Track: Provide extruded aluminum cubicle track with white acrylic electrostatic finish. Section size is 3/4" high by 1-3/8" wide. Track to be prefabricated to shape in one continuous piece whenever possible. Corner radius to be 12".
- B. Curtain Carriers: Provide curtain carriers with virgin nylon bodies, stainless steel bead chain and hard aluminum hooks.
- C. Track End Stops: Provide molded thermoplastic end stops for all track section ends.
- D. Track Attachment: Provide appropriate hardware accessories as required for attachment to suspended ceiling grid.

2.3 CURTAIN MATERIAL

- A. Provide Windsor Cubical cloth 72" wide.
 - a. Color: Selected by Owner/Architect from manufacturer's complete color line
 - b. 100% Trevira Polyester, inherently Flame Retardant Finish (to meet all fire safety codes)
 - c. Mesh shall be flame retardant, 100% washable Nylon with 1/2" openings.
- B. Standard Manufacturing Details
 - a. Top hem is Triple Thick 1 1/2" wide.
 - b. Side hem is Double Thick 1/2" wide.
 - c. Bottom hem is Double Thick 1 1/2" wide.
 - d. Rust Proof aluminum grommets 6" apart.
 - e. Vertical seams are 2" needle, locked-stitched overlapped.
- C. Typical curtain dimensions (for typical ceiling heights from 8'-0" to 10'-0')
 - a. Curtain to be 15" A.F.F.
 - b. Nylon mesh to be 21" in height.
 - c. Curtain Cloth height varies based on actual ceiling height.
 - d. Overall curtain width to be 10% greater than the length of finished track.

3 PART 3 EXECUTION

3.1 SURFACE CONDITIONS

- A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.2 INSTALLATION

- A. Install the work of this Section in strict accordance with the manufacturer's recommendations.
- B. Install curtains after final cleaning has been completed.

END OF SECTION