

SECTION 23 30 00

DUCTWORK AND ACCESSORIES

PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. The drawings and the specifications including Section 23 05 00 "Supplemental Mechanical General Requirements" are hereby made a part of the work of this section.
- B. Drawings and general provisions of Contract including General and Supplementary Conditions and all Division 1 specification sections.
- C. Provision of waste management: Section 01 74 19, Construction Waste Management and Disposal.

1.2 DESCRIPTION OF WORK

- A. The work covered by this Section of the specifications includes the furnishing of labor, materials, equipment, transportation, permits, inspections and incidentals and the performing of operations required to install the ductwork systems indicated.

1.3 SUBMITTALS

- A. Substitutions: Your attention is directed to Section 23 05 00-"Substitutions", relative to competition and the (ONLY) notation. Familiarity with this section should be achieved before reading the PRODUCTS section of this specification.
- B. The items for which the submittals paragraph in Section 23 05 00, Supplemental General Mechanical Requirements, apply are as follows:
 - 1. Ductwork.
 - 2. Ductwork accessories.
 - 3. Firestopping materials and methods.
 - 4. Ductwork sealing products.
 - 5. Grilles and diffusers.
- C. Section 01 33 00 - Submittal Procedures: Submittal procedures.
- D. Product Data: Submit data on product characteristics, performance criteria and limitations.
- E. Manufacturer's Installation Instructions: Submit procedure for preparation and installation.
- F. Manufacturer's Certificate: Certify products meet or exceed specified requirements.

PART 2 PRODUCTS

2.1 DUCTWORK

- A. Classification of Ductwork: Low pressure ductwork: up to 2" W.G. static pressure.
- B. Materials: Unless otherwise indicated low pressure ductwork shall be galvanized steel. Galvanized sheet metal shall be new galvanized steel sheets of lock forming quality with zinc coating that will not flake or peel under forming operation.

- C. Construction for Low Pressure Round and Rectangular Ductwork:
1. Material: Galvanized steel conforming to ASTM A527, weight of galvanized coating shall be not less than 1-1/4 ounces total for both sides of one sq.ft. of a sheet. Construction, metal gage, and reinforcements shall conform with SMACNA "Duct Construction Standards" and NFPA 90A for 2" W.G. pressure class.
 2. Fittings: Shall be constructed in accordance with SMACNA Standards and shall be of the types indicated (ONLY). Taps and take-offs shall be at 45 degrees.
 3. Longitudinal joints shall be Pittsburgh lockseam (ONLY). Button punch snap locks are not acceptable.
 4. Joints shall be sealed to SMACNA seal class B.

2.2 DUCTWORK ACCESSORIES

- A. Access Doors: Ruskin Model ADC2, 12"x12" size, 24 gauge galvanized steel, steel on both sides of door, foam gasket seals, 1" insulation, 2 cam locks, no hinge.
- B. Backdraft Dampers (BDD): Ruskin Model CBD2 or American Warming and Ventilating aluminum frame and blades, extruded vinyl edge seals, field set at 0.10" W.G. pressure differential for full open operation.
- C. Flexible Duct Connections: Ventfabrics, Inc. neoprene coated glass fabric.
- D. Drawbands for Flexible Ducts: Clinch type stainless steel with screwdriver adjustment, or nylon with lever action tightening tool provided by the drawband manufacturer.
- E. Turning Vanes: (Low Pressure):
1. Solid blade, mounted with the long edge down stream in accordance with duct construction details indicated. Submit a 12"x12" sample elbow for review prior to fabrication.
- F. Volume Dampers:
1. Factory fabricated as specified, or shop fabricated in accordance with SMACNA "HVAC Duct Construction Standards".
 2. Rectangular: Ruskin Model MD-35, or American Warming and Ventilating, 12 gauge galvanized steel, locking quadrant, opposed blade over 11", single blade 11" and under.
 3. Round: Ruskin Model MDRS25, or American Warming and Ventilating, 20 gauge galvanized steel with locking quadrant(ONLY). Dampers may be provided integral with spin-in fittings.
- I. Flexible Ductwork:
1. Low Pressure Duct Systems: Wiremold type WGCF, polyester core with wire helix, 2" thick (R-6 min.), 3/4 lb fiberglass insulation, polyolefin jacket/vapor barrier, 2" W.G. rated pressure.
- J. Joint Sealer:
1. Hardcast Two-Part II DT tape with RTA-50 indoor/outdoor activator.

2. Hardcast Duct-Seal 321 water based indoor/outdoor sealant.
- K. Acoustical duct liner for rectangular ductwork shall be Type AP Armaflex SA duct liner. The liner shall be elastomeric unicellular (closed cell) and have a thermal conductivity of 0.27 Btuh/°F.-sf-in. and be cleanable and suitable for duct velocities of 4000 FPM. Duct liner thickness shall be 1" unless indicated otherwise. The installation shall include 100% coverage of the manufacturer's recommended adhesive and protective Z-strips at all exposed upstream edges. Mechanical fasteners shall be used in addition to adhesive. Insulation shall comply with NFPA 90A and NFPA 90B and be approved by Factory Mutual. Duct dimension are net inside of liner.
- 2.3 AIR DEVICES (Krueger, Price, Anemostat, Metal Aire, Titus) ONLY
- A. Material and Finishes: Construct diffusers, registers, and grilles of aluminum. Exterior and exposed edges shall be rolled, or otherwise stiffened and rounded. Steel parts shall be factory zinc-phosphate treated prior to priming and painting or have a baked-on enamel finish. Aluminum parts shall be finish painted. Provide frame style compatible with ceiling or wall type. Colors shall be selected by the Architect. Devices to be installed on exposed duct installations shall be furnished in primer suitable for field application of color coat.
 - B. Sound Pressure Level: Manufacturer certified sound pressure level rating of inlets and outlets in accordance with ADC 1062 R4. Conform with the permissible room sound pressure level for each device as scheduled.
 - C. Throw: Defined as distance from the diffuser, register, or grille to the point which the resultant room air velocity is 50 to 35 feet per minute.
 - D. Ceiling Diffusers / Linear Slot Diffusers: Equip with core styles required to provide air distribution pattern indicated. Internal parts shall be removable through the diffuser-neck for access to the duct and without the use of special tools. Construct each diffuser of four or more concentric elements designed to deliver air in a generally horizontal direction. The interior elements of square and rectangular ceiling diffusers may be square or rectangular as manufacturer's standard. Screws or bolts in exposed face of frames or core elements are not acceptable. Diffusers shall have an opposed blade volume damper in the diffuser neck. Diffusers shall have a 24"x24" lay-in panel for areas with acoustical ceilings and surface-mount frame for GWB ceilings. Ceiling diffusers shall be Metalaire Series 5000 with induction vane (IV) option, Titus or Price. Linear slot ceiling supply diffusers shall be 4'-0" long, 4-slot, 1" slots, extruded aluminum, adjustable pattern controllers, integral boot plenum with ½" thick insulation.
 - E. Grilles and Registers: Construction and finish as indicated, 1/2" louver spacing, 45° curved blade. Registers shall have opposed-blade volume dampers with screwdriver adjuster. Unless otherwise indicated, registers shall be provided. Linear bar grilles shall be heavy-duty construction suitable for floor applications.
 - F. Ceiling grille and register construction shall be aluminum, with a white powder coated matte finish. Linear bar floor grilles and sidewall grilles shall have a clear anodized finish.
 - G. General: The interior of all sheetmetal connections to grilles, registers and diffusers shall be painted with a non-specular flat black paint so that no sheetmetal surfaces are visible from the finished space.

PART 3 EXECUTION

3.1 SURFACE CONDITIONS

- A. Inspection:

1. Prior to work of this Section, carefully inspect the installed work of other trades and verify that such work is complete to the point where this installation may properly commence.
2. Verify that the duct systems may be installed in accordance with pertinent codes and regulations and the reviewed Submittals.

3.2 INSTALLATION OF DUCTWORK AND AIR DEVICES

- A. Provide and erect in accordance with the best practice of the trade ductwork shown on the drawings and as required to complete the intended installation. Make offsets as shown or required to place ductwork in proper position to avoid conflicts with other work and to allow the application of insulation and finish painting to the satisfaction of the Architect. Sizes given are "inside - clear" dimensions and not necessarily that of sheet metal. Ducts shall be arranged to adjust to "field conditions". The Sheet Metal trades shall coordinate his work with other trades. Work shall conform to ASHRAE duct construction recommendations, SMACNA "Duct Construction Standards", NFPA, and the requirements of MUBEC.
- B. Joint Sealing: See PRODUCTS section.
- C. Longitudinal joints: See PRODUCTS section.
- D. Turns shall be made with long radius elbows or, if physically impossible to use long radius elbows, shall be square turns with specified turning vanes. CAUTION: Turns not conforming to this requirement shall be ordered removed and replaced with properly built turns.
- E. Access Doors: Provide access doors for concealed apparatus requiring service and inspection in the duct system including but not limited to dampers, sensors and motors, and upstream and downstream from duct coils.
- F. Duct Sleeves and Prepared Openings: Install duct sleeves and prepared openings for duct mains, duct branches, and ducts passing through walls, roofs, and ceilings. Insure the proper size and location of sleeves and prepared openings. Allow one-inch clearance between duct and sleeve or one-inch clearance between insulation and sleeve for insulated ducts, except at grilles, registers, and diffusers.
- G. Duct Supports: Unless otherwise indicated, provide one-inch wide by 16 gage galvanized steel sheet metal strips on each side of ducts. Anchor risers in the center of the vertical run to allow ends or riser free vertical movements. Attach supports only to structural framing members. Do not anchor supports to metal decking unless a means is provided (architectural review required) for preventing the anchors from puncturing the metal decking. Where supports are required between structural framing members, provide suitable intermediate metal framing. Where C clamps are used, use retainer clips.
- H. Flexible Collars and Connections: Provide flexible collars between fans and ducts or casings and where ducts are of dissimilar metals, as indicated or required. For round ducts, securely fasten flexible connections using stainless steel clinch-type draw-band. Nylon drawbands may be used if installed using the drawband manufacturer's lever-action tightening tool. For rectangular ducts, lock flexible connections to metal collars.
- I. Flexible Ducts: Provide where indicated. No fiberglass shall be in contact with air flow. Flexible duct length shall not be more than 4'-0". Install with metal band hangers and without excess length, provide maximum extension of flex duct. Securely fasten flexible ducts to metal collars using a stainless steel or tool-tightened nylon drawband on the duct core and a second drawband on the insulation vapor barrier. If the duct exceeds 12 inches diameter,

position the drawband behind a bead on the metal collar. Taping in lieu of drawbands is not allowed.

- J. Any deviation in the duct system must be submitted as a shop drawing and stamped. CAUTION: Any deviation not submitted and favorably reviewed will be ordered removed from the system and replaced with that which is shown on the Drawings.
- K. Discrepancies between actual field conditions and the Contract Documents shall be brought to the attention of the Architect prior to fabrication.
- L. Field Changes to Ductwork: Field changes of ducts such as those required to suit the sizes of factory-fabricated equipment actually furnished shall be designed to minimize expansion and contraction. Use 4:1 transitions in field changes as well as modifications to connecting ducts.
- M. Transitions with a slope greater than 4 to 1 shall be ordered removed from the system and replaced with a transition which meets this criteria.
- N. Joints and seams at intake and exhaust plenums and joints on intake and exhaust ductwork for a distance of 3 feet from the plenum shall be sealed watertight on the bottom and side joints and seams.
- O. Isolation dampers at intake and exhaust louvers and vent hoods shall be sealed to the ductwork to provide an airtight assembly with similar performance characteristics to the isolation damper.

3.3 CLOSING IN WORK

- A. Cover up or enclose work after it has been properly and completely tested and reviewed.
- B. No additional cost to the Owner will be allowed for uncovering or recovering any work that is covered or enclosed prior to required test and review.

3.4 TEST AND ADJUST

- A. Before operating any system, the system shall be cleaned out to remove dust and foreign materials.
- B. After the installation is complete and ready for operation, test the system under normal operating conditions in the presence of the Architect and demonstrate that the system functions as designed.
- C. Correct defects which develop during the test period, conduct additional testing until defect free operation is achieved.

3.5 CLEANUP AND CORROSION PREVENTION

- A. Ductwork and equipment shall be thoroughly cleaned. Dirt, dust, and debris shall be removed and the premises left in a clean and neat condition.
- B. Before covering is applied to duct systems, clips, rods, clevises and other hanger attachments, and before uncovered piping is permitted to be concealed, corrosion and rust shall be wire brushed and cleaned and in the case of iron products, a coat of approved protective paint applied to these surfaces.

3.6 INSTRUCTIONS

- A. On completion of the project, instruct the Owner's representative in the care and operation of the system. The total period of instruction shall not exceed four (4) hours. The time of instruction shall be arranged with the Owner. In addition to the prime Mechanical Contractor, the control system Contractor, Balancing Contractor, and Owner's representative shall be present and participate in the Owner's instruction.

3.7 FIRESTOPPING

- A. Firestopping shall be performed in accordance with Specification Section 07 84 00 "Firestopping". All penetrations of fire-rated assemblies including walls and floors by mechanical system components (piping, ductwork, conduits, etc.) shall be firestopped as specified.

* END OF SECTION *