



FOOTING SCHEDULE				
TYPE	LENGTH	WIDTH	DEPTH	REINFORCING
F4	4'-0"	4'-0"	1'-0"	(5)-#4 BOTTOM E.W
F5	5'-0"	5'-0"	1'-0"	(6)-#4 BOTTOM E.W
F6	6'-0"	6'-0"	1'-0"	(7)-#4 BOTTOM E.W

- NOTES:**
- STRUCTURAL SLAB IS 4" SLAB-ON-GRADE. SEE TYPICAL DETAILS. REFERENCE FINISH FLOOR ELEVATION OF 49'-0", ASSUMED.
 - TOP OF CONCRETE WALL ELEVATION 49'-0", U.N.O.
 - TOP OF FOOTING ELEVATION VARIES, SEE PLAN.
 - T/PIER ELEV. 48'-0", U.N.O.
 - PROVIDE MIN. (2) STUDS IN WALL @ EACH CORNER FOR HOLD-DOWNS.
 - SW-"X" DENOTES SHEAR WALLS. SHEAR WALLS SHOWN ON THIS FOUNDATION PLAN. FOR ADDITIONAL SHEAR WALLS, SEE S1.2.
 - SEE TRACK ATTACHMENT TO FOUNDATION WALL @ SHEAR WALLS THIS DWG.
 - SEE DWG S1.2 FOR HOLD-DOWN LOCATIONS AND ADD'L INFORMATION.
 - "F" DENOTES FOOTING TYPE, SEE FOOTING SCHEDULE THIS DWG.
 - "P" DENOTES PIER TYPE, SEE PIER DETAILS ON SHEET S2.2.
 - "B" DENOTES BASEPLATE TYPE, SEE BASEPLATE DETAILS ON SHEET S2.2.
 - DENOTES SIMPSON HOLD DOWN.
 - STEEL STUD TRACK TO BE 16 GA. AND ATTACHED TO FOUNDATION WITH (2) HILTI X-DNI PAF'S AT 16" o.c. w 1 1/4" EMBED.

REVISIONS		ISSUE	DATE	ISSUE
No.	DATE	FOR PERMIT		
A	3-19-07			

SHEET TITLE:
FOUNDATION PLAN

DESIGNED: SM
 DRAWN: PM
 DATE: 2-7-07
 CADD FILE: 7016-S1.DWG
 PROJECT NUMBER: 7016