



Stepped flashing and counter flashing will be installed where chimney meets gable

In accordance with IRC 2009, ash cleanout openings will be within 6" of the base of each flue
The top of each opening will be more than 6" away from the respective inlets/thimbles
The openings will be greater than 6" high
The openings will be fitted with cast iron doors

Ash cleanout door for right flue

Ash cleanout door for left flue