



Living Room

Living Room

Two Temporary 2x4 Walls will be built on Either side of EXG. Load Bearing to support 2nd Floor while Demo and installation happen.

New (4) 2x4 Post Aligned w/ EXG. Lally Column in Basement.

New (4) 2x6 Post on top of Ext. Concrete wall

Remove EXG. Bearing Wall, Replaced with Triple 1.75" x 9.5" LVL. To support 2nd Floor 2x10 Floor Joists.

13'6"

24'

12'

1st Floor Proposed Floor Plan w/ New Beam To Support 2nd Floor Joists