35 Winding Way
Portland, ME

House Rough Dimensions (not to scale)
with Heat Pump unit locations

Inspections Division
Date: 09/03/13

Notes:
Home is built of traditional wood framing and is sufficient to support the additional load of the equipment being installed.

Two indoor units. Each weighing 22 lbs. One unit located on first floor in living room. The other unit located on second floor in master bedroom.

Units to be mounted to wall framing with 2.5" fasteners sufficient to support the unit.

Two outdoor unit locations. Each weighs 88 lbs. Wall bracket to support unit and shall be lagged into wall framing.

Minimum of 4 3" stainless steel lag bolts per wall bracket.