

DOOR SCHEDULE: First Floor

Mark	Location	Size	Frame Data	Door Data	HW Set	Notes
101	Exterior to Vestibule	Existing to Remain				
102	Vestibule to Lobby	Existing to Remain				
103	Lobby to Bath	Existing to Remain				
104	Lobby to Bath	Existing relocated				
105	Waiting to Corridor	3070	HM 16 ga	Wood: full glass	LHR	Sidelight Frame
106	Reception to Manager	3070	HM 16 ga	Wood: half glass	RH	Lock
107	Corridor to Reception Office	3070	HM 16 ga	Wood: half glass	RH	Passage
108	Corridor to Stair	3070	HM 16 ga	HM: narrow light	RHR	Lockset
109	Corridor to Dr Office	3070	HM 16 ga	Wood: Full glass	LH	Lockset
110	Corridor to Operator	3070	HM 16 ga	Wood: TBD	LHR	Passage
111	Corridor to Operator	3070	HM 16 ga	Wood: TBD	RHR	Passage
112	Corridor to Operator	3070	HM 16 ga	Wood: TBD	LHR	Passage
113	Corridor to Operator	3070	HM 16 ga	Wood: TBD	LHR	Passage
115a	Corridor to Stair	3070	HM 16 ga	HM: narrow light	RHR	Lock
114	Corridor to Operator	3070	HM 16 ga	Wood: TBD	LHR	Passage
116	Corridor to Operator	3070	HM 16 ga	Wood: TBD	LHR	Passage
117	Corridor to Break Room	3070	HM 16 ga	Wood: Full glass	RHR	Passage
118	Changing Room	Existing to Remain				
119	Changing Room	Existing to Remain				
120	Boy Scout Shop Entry	Existing to Remain				
121	Break Room to Stair	3070	HM 16 ga	HM: narrow light	RHR	Lock
122	Locker Room to Bath	3070	HM 16 ga	Wood: flush	RH	Privacy
123	Closet	3070	HM 16 ga	Wood: flush	RHR	Passage
124	Storage	3070	HM 16 ga	Wood: flush	RH	TBD
125	Lobby to Recovery	3070	HM 16 ga	HM: Flush	LH	Lock
126	Single Recovery	3070	HM 16 ga	Wood: TBD	RHR	Passage
127	Elevator Lobby to Waiting	3070	HM 16 ga	Wood: full glass	RHR	Lock