

DOOR SCHEDULE: Second Floor

Mark	Location	Size	Frame Data	Door Data	HW Set	Notes
201	Waiting to Reception	3070	HM 16 ga	Wood: full glass	RHR Lock	Sidelight frame
202	Elevator lobby to waiting	3070	HM 16 ga	Wood: full glass	RHR Lock	Sidelight frame
203	Elevator lobby to Storage		Existing door and frame to remain			
204	Elevator to bath		Existing door and frame to remain			
205	Rental space to bath		Existing door and frame to remain			
206	Elevator lobby to Rental	3070	HM 16 ga	Wood: Full glass	LH Lock	
207	Elevator lobby to Lab	3070	HM 16 ga	Wood: narrow light	RH Lock	
208	Corridor 1 to Closet	6070	HM 16 ga	Wood: flush	N/A	Ball catch
209	Corridor 1 to Corridor 2	3070	HM 16 ga	Wood: half light	RH	passage
210	Corridor 1 to Bath	3070	HM 16 ga	Wood: flush	RH	privacy
211	Corridor 1 to Stair		Existing door and frame to remain			
212	Corridor 2 to Office	3070	HM 16 ga	Wood: half light	RH	Lock
213	Corridor 2 to Bath		Existing door and frame to remain			
214	Break Room to Lockers	3070	HM 16 ga	Wood: flush	LH	passage
215	Reception to Break room	3070	HM 16 ga	Wood: half light	LH	passage
216	Lab to Stair		Existing door and frame to remain			
217	Stair to Rental Space	3070	HM 16 ga	HM: narrow light	RH	Lock
218	Lab to Lab Bath	3070	HM 16 ga	Wood: flush	RH	privacy
219	Lab to Lab Office	3070	HM 16 ga	Wood: half light	LH	Lock
220	Lab Corridor to Fabrication	3070	HM 16 ga	Wood: half light	LH	Lock
221	Lab Corridor to Corridor 1	3070	HM 16 ga	Wood: TBD	LH	passage
222	Corridor 1 to Work Area	3070	HM 16 ga	Wood: TBD	RH	passage
223	Corridor 1 to Tech	3070	HM 16 ga	Wood: TBD	RH	Lock
224	Corridor 1 to Storage	3070	HM 16 ga	Wood: flush	RHR	Lock
225	Closet	3070	HM 16 ga	Wood: flush	RHR	Passage
226	Corridor 3 to Bath	3070	HM 16 ga	Wood: flush	LH	privacy
227	Corridor 3 to Office	3070	HM 16 ga	wood: TBD	LHR	passage

Door pending salvage