# THIRD FLOOR ROOM FINISH SCHEDULE

| ROOM NUMBER | ROOM NAME | FLOOR | BASE | WALLS | | | | CEILING | | ROOM NUMBER | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | NORTH | SOUTH | EAST | WEST | MATERIAL | HEIGHT | | |
| 301 | GALLERY | CPT | WD | GWB/WSC | GWB/WSC | GWB/WSC | GWB/WSC | GWB/ACT | 9'-6"/8'-6" | 301 | |
| 301a | ALCOVE | CPT | WD | VWC | VWC | VWC/WSC | VWC | ACT | 9'-0" | 301a | |
| 302 | MEN'S TOILET | CT | CT | CT/GWB | CT/GWB | CT/GWB | CT/GWB | ACT | 9'-0" | 302 | |
| 303 | WOMEN'S TOILET | CT | CT | CT/GWB | CT/GWB | CT/GWB | CT/GWB | ACT | 9'-0" | 303 | |
| 304 | STAIR | RUBBER | RES | GWB | GWB | GWB | GWB | EXP | N/A | 304 | |
| 305 | STAIR | RUBBER | RES | GWB | GWB | GWB | GWB | EXP | N/A | 305 | |
| 306 | TEL/DATA | VCT | RES | GWB | GWB | GWB | GWB | EXP | N/A | 306 | |
| 307 | ELEC. | VCT | RES | GWB | GWB | GWB | GWB | EXP | N/A | 307 | |
| 308 | JAN. | VCT | RES | FRP | FRP | FRP | FRP | GWB | 8'-0" | 308 | |
| 309 | SUPPLIES | VCT | RES | GWB | GWB | GWB | GWB | GWB | 8'-0" | 309 | |
| 310 | AUTHORITY ROOM | CPT | WD | GWB/WSC | GWB/WSC | GWB/WSC | GWB/WSC | GWB/ACT* | 9'-6"/8'-6" | 310 | *SEE WALL SECTIONS |
| 311 | CLOSET | CPT | RES | GWB | GWB | GWB | GWB | GWB | 8'-0" | 311 | |
| 312 | CLOSET | CPT | RES | GWB | GWB | GWB | GWB | GWB | 8'-0" | 312 | |
| 313 | CORRIDOR | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 313 | |
| 314 | KITCHEN | VCT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 314 | |
| 315 | STORAGE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 315 | |
| 316 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 316 | |
| 317 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 317 | |
| 318 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 318 | |
| 319 | WAIT | CPT | RES | – | GWB | GWB | GWB | ACT | 9'-0" | 319 | |
| 320 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 320 | |
| 321 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 321 | |
| 322 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 322 | |
| 323 | VAULT | VCT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 323 | |
| 324 | OPEN OFFICE | CPT | RES | – | GWB | GWB | GWB | ACT | 9'-0" | 324 | |
| 325 | COPY | VCT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 325 | |
| 326 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 326 | |
| 327 | CORRIDOR | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 327 | |
| 328 | TEST | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 328 | |
| 329 | AUDIT | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 329 | |
| 330 | WAITING | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 330 | |
| 331 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 331 | |
| 332 | FILES | VCT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 332 | |
| 333 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 333 | |
| 334 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 334 | |
| 335 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 335 | |
| 336 | CORRIDOR | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 336 | |
| 337 | FILE STORAGE | VCT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 337 | |
| 338 | CONFERENCE | CPT | WD | GWB/RAIL | GWB/RAIL | GWB/RAIL | GWB/RAIL | ACT | 9'-0" | 338 | |
| 339 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 339 | |
| 340 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 340 | |
| 341 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 341 | |
| 342 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 342 | |
| 343 | LAYOUT | CPT | RES | GWB | GWB | – | GWB | ACT | 9'-0" | 343 | |
| 344 | OPEN OFFICE | CPT | RES | GWB | GWB | GWB | – | ACT | 9'-0" | 344 | |
| 345 | CONFERENCE | CPT | WD | GWB/RAIL | GWB/RAIL | GWB/RAIL | GWB/RAIL | ACT | 9'-0" | 345 | |
| 346 | OFFICE | CPT | WD | GWB/RAIL | GWB/RAIL | GWB/RAIL | GWB/RAIL | GWB/ACT | 9'-0" | 346 | |
| 347 | TOILET | CT | CT | GWB/CT | GWB/CT | GWB/CT | GWB/CT | ACT | 8'-0" | 347 | |
| 348 | STOR. | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 348 | |
| 349 | OPEN OFFICE | CPT | WD | GWB/RAIL | GWB/RAIL | GWB/RAIL | GWB/RAIL | ACT | 9'-0" | 349 | |
| 350 | CLOSET | CPT | RES | GWB | GWB | GWB | GWB | GWB | 9'-0" | 350 | |
| 351 | OFFICE | CPT | RES | GWB | GWB | – | GWB | ACT | 9'-0" | 351 | |
| 352 | CORRIDOR | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 352 | |
| 353 | OFFICE | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 353 | |
| 354 | CORRIDOR | CPT | RES | GWB | GWB | GWB | GWB | ACT | 9'-0" | 354 | |

## GENERAL NOTES:

1. SEE G1001 FOR PROJECT GENERAL NOTES.

## FINISH NOTES:

1. SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION REGARDING FINISH MATERIALS.
2. REFER TO PARTITION LEGEND FOR TYPE OF GWB COMPOSITION REQUIRED. "ABUSE RESISTANT", "MOISTURE RESISTANT" OR OTHER (TYPICAL).
3. REFER TO INTERIOR ELEVATIONS FOR MORE INFORMATION ON MATERIAL LOCATIONS

## FINISH ABBREVIATIONS:

| | |
|---|---|
| ACT | ACOUSTICAL CEILING TILE |
| CONC | CONCRETE, SEALED |
| CEM | CEMENT BOARD |
| CPT | CARPET |
| CT | CERAMIC TILE |
| EXP | EXPOSED STRUCTURE |
| FRP | FIBERGLASS REINFORCED PANEL |
| GWB | GYPSUM WALLBOARD, PAINTED |
| INS | INSULATED |
| MAT | WALK-OFF MAT |
| PF | PRE-FINISHED BY MANUFACTURER |
| PLAM | PLASTIC LAMINATE |
| PTD | PAINTED |
| QT | QUARRY TILE |
| RB | RUBBER BASE |
| RCP | REFLECTED CEILING PLAN |
| RES | RESILIENT BASE |
| SF | STOREFRONT (ALUMINUM) |
| SV | SHEET VINYL |
| VCT | VINYL COMPOSITION TILE |
| VWC | VINYL WALL COVERING |
| WD | WOOD |
| WDP | WOOD PANELING |
| WP | WALL PROTECTION |
| WSC | WOOD WAINSCOT |


SMRT
ARCHITECTURE ENGINEERING PLANNING
SMRT
144 Fore Street/P.O. Box 618
Portland, Maine 04104
tel. (207) 772-3846
fax. (207) 772-1070


PROJECT TITLE:
MAINE TURNPIKE AUTHORITY
ADMINISTRATION BUILDING
PORTLAND, MAINE

CURRENT ISSUE STATUS:
ISSUED FOR BIDDING/CONSTRUCTION
7-9-07

| REV | DESCRIPTION | DATE |
|---|---|---|
| 0 | BIDDING/CONSTRUCTION | 7-9-07 |

GRAPHIC SCALE: 0" 1"

| | |
|---|---|
| SCALE: | AS NOTED |
| PROJECT MANAGER: | SLB |
| JC/DRAWN BY: | TCM/TCM |
| A/E OF RECORD: | SLB |
| CAD FILE: | AE603-06016 |
| PROJECT NO: | 06016 |
| DATE: | 7-9-07 |

SHEET TITLE:
THIRD FLOOR ROOM FINISH SCHEDULE

SHEET No.
AE603

© COPYRIGHT 2007 SMRT INC

A1 THIRD FLOOR ROOM FINISH SCHEDULE

NONE – *