ELEC/HVAC PLAN

SCALE: 3/16"=1'-0"

IC J-BOXES @ 48" & 80" A.F.F. FOR INTERCOM SYTESM
(48" BOX: 2x4 SINGLE GANG)
(80" BOX: 4x4 DOUBLE GANG)

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 01/11/16

ELECTRICAL SYMBOLS

- DUPLEX RECEPTACLE @ 16" A.F.F.
- DUPLEX RECEPTACLE @ 42" A.F.F. (UNLESS NOTED)
- QUADPLEX RECEPTACLE @ 16" A.F.F. (UNLESS NOTED)
- RECPTACLE 240v @ 16" A.F.F.
- CEILING MOUNTED DUPLEX RECEPTACLE
- CEILING MOUNTED QUADPLEX RECEPTACLE
- FLOOR DUPLEX RECEPTACLE
- FLOOR QUADPLEX RECEPTACLE
- SWITCH @ 48" A.F.F.
- 3-WAY SWITCH @ 48" A.F.F.
- ELECTRICAL PANEL BOX 48" TO BOTTOM
- TELEPHONE JACK AT 16" A.F.F. (UNLESS NOTED)
- TELEPHONE JACK AT 42" A.F.F. (UNLESS NOTED)
- TELEPHONE FLOOR J-BOX
- COMPUTER JACK @ 16" A.F.F. (UNLESS NOTED)
- W.P. WEATHERPROOF PHOTOCELL
- WALL MOUNTED JUNCTION BOX 16" (UNLESS NOTED)
- CEILING MOUNTED JUNCTION BOX
- FLOOR MOUNTED JUNCTION BOX
- T PROGRAMMABLE A/C THERMOSTAT @ 53" A.F.F.
- P J-BOX @ 48" A.F.F. FOR PULL STATION - TO BE WIRED BACK TO HORN/STROBE (2x4 SINGLE GANG)
- H J-BOXES @ 48" & 80" A.F.F. FOR PULL STATION AND HORN/STROBE (48" BOX: 2x4 SINGLE GANG) (80" BOX: 4x4 DOUBLE GANG)
- S J-BOX @ 80" A.F.F. FOR STROBE ONLY (4x4 DOUBLE GANG)
- EXIT ILLUMINATED EXIT SIGN AND EMERGENCY LIGHTING COMBO w/BATTERY BACK-UP
- EXHAUST FAN-100 CFM (UNLESS NOTED)
- EXHAUST FAN & LIGHT COMBO-100 CFM/26W (UNLESS NOTED)
- 1'x4' FLUORESCENT - DIFFUSED - SURFACE MOUNTED (2 TUBE = 64w MAX.)
- INCANDESCENT SP FIXTURE (26w)
- RECESSED INCANDESCENT LIGHT FIXTURE (26w)
- W.P. WEATHERPROOF LIGHT "PORCH" (W. PER SPEC)
- W.P. WEATHERPROOF LIGHT "FLOOD" (W. PER SPEC)
- D HVAC DISCONNECT

ELECTRICAL PANEL SCHEDULE PANEL "B"

CIRCUIT	NOMENCLATURE	BREAKER (AMPS)	WIRE (CU.)
1/3 2/4	HVAC UNIT	60A(2P)	6-3 SE THHN
5,6	LIGHTS	20A	12-2 NM THHN
7-10	RECPTS	20A	12-2 NM THHN
11	LIGHTS & FANS	20A	12-2 NM THHN
12/14	DED RECEPT	30A(2P)	10-3 NM ROMEX

ELECTRICAL PANEL SIZING PANEL "B"

DESCRIPTION		KVA
.0035 kW/SF x 1870 SF x 1.25	=	8.18
30 RECEPTS @ 180 VA / 1000	=	5.40
1 WATER HEATER @ 6.5 kW	=	6.50
2 FANS @ .3 kW x 1.25	=	.75
2 HVAC @ 15.50 kW (EA.)	=	31.00
51.83 TOTAL kW		
TOTAL / 240 x 1000	=	215.96 AMPS
INSTALL 225 AMP PANEL		
120/240 V, 1Ø PHASE		

PETER LEE, P.E. M.S.
ENGINEERING INTERNATIONAL, INC.
ENGINEER: PETER LEE, P.E., M.S.
CONSULTING ENGINEER
23329 CENTURY DRIVE
ELKHART, IN 46514

STATE OF MAINE
PIN-SHI PETER LEE
No.12156
LICENSED PROFESSIONAL ENGINEER
Nov. 11, 2015

SCHIAVI
Smarter Modular Solutions

SCHIAVI LEASING
JENNIFER CURRIER
103 AIRPORT ROAD
OXFORD, ME 04270
PH: (207) 539-8211
FAX:
WWW.VANGUARDMODULAR.COM

ELEC / HVAC PLAN

SERIAL #: 1386 A-B
OCCUP: E
DRAWING #: VGM-2015-0027

This document and all information contained herein, are the proprietary data and trade secrets of Vanguard Modular Building Systems (VMBS), and Schiavi Leasing Corporation (Schiavi). This document and the information contained herein may not be reproduced, used, or disclosed in any manner, or to any extent. Written authorization by a current employee of VMBS or Schiavi must be obtained prior to use of this information, in any form, including that which is represented by this complete page.

Drawing Date: 11-10-2015	Project: PORTLAND, ME
Drawn By: J.L.B.	Sheet: E/H1
Scale: 3/16"=1'-0"	5 of 6