

COPYRIGHT 2016 © DIRIGO ARCHITECTURAL ENGINEERING LLC. ALL RIGHTS RESERVED. NO REPRODUCTION WITHOUT PRIOR WRITTEN PERMISSION

GENERAL NOTE:
 GENERAL CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS AT THE JOB SITE AND REPORT ANY VARIATIONS OR DISCREPANCIES BETWEEN THE DRAWINGS AND EXISTING CONDITIONS TO ARCHITECT PRIOR TO COMMENCING WORK

DOOR HARDWARE SCHEDULE

ITEM	RECOMMENDED MANUFACTURER/ MODEL OR APPROVED EQUAL	DOOR													
		D01	D02	D03	D04	D05	D06	D07	D08	D09	D10	D11	D12	D13	D14
HINGES	SEE SPECIFICATION 087100	X		X	X	X	X	X	X			X	X		
LOCKSETS/HANDLES		X		X	X	X	X	X	X			X	X		
EXIT DEVICES															
DOOR CLOSERS		X	N/A	X	X	X	X	X	X	N/A	N/A	X			
DOOR STOPS		X		X	X	X	X	X				X			
AUTOMATIC DOOR OPENER															
PUSH BUTTON DIGITAL LOCK												X		X	X
MAGNETIC DOOR HOLDERS									X						

DOOR SCHEDULE

MARK	ROOM NUMBER + NAME	DOOR SIZE					ELEVATION	MATERIAL	RATING (MINUTES)	RECOMMENDED MANUFACTURER/MODEL	COLOR	FRAME		NOTES
		WIDTH	HEIGHT	THICKNESS	MATERIAL	ELEVATION						COLOR TO MATCH EXISTING		
D01	VACUUM BOOTH	3'-0"	6'-8"	1 3/4"	B	METAL	20				METAL	1	PRIMED	
D02	SOILED PPE ROOM	1'-6"	1'-6"	1 3/4"	A	METAL	20	OSWALD			METAL	1	PRIMED	LAUNDRY DOOR: SELF-CLOSING, SELF-LATCHING, STAINLESS, BOTTOM-HINGE, RUBBER SAFETY BAFFLE
D03	SOILED PPE ROOM	2'-8"	6'-8"	1 3/4"	A	METAL	20				METAL	1	PRIMED	
D04	BATHROOM	3'-0"	7'-0"	1 3/4"	A	METAL	20				METAL	1	PRIMED	
D05	BATHROOM	3'-0"	7'-0"	1 3/4"	A	METAL	20				METAL	1	PRIMED	
D06	CLEAN LINEN	3'-0"	7'-0"	1 3/4"	B	WOOD	20				METAL	1	PRIMED	
D07	CORRIDOR	(1) 3'-0" + (1) 1'-6"	7'-0"	1 3/4"	B	WOOD	20				METAL	1	PRIMED	DOUBLE DOORS. 4'-6" TOTAL WIDTH. COORDINATE MAGNETIC DOOR HOLDERS W/ DIV. 26 ELECTRICAL/FIRE ALARM
D08	LAUNDRY	3'-0"	7'-0"	1 3/4"	A	WOOD	20				METAL	1	PRIMED	
D09	MEN'S LOCKERS	1'-6"	1'-6"	1 3/4"	A	WOOD	90	OSWALD			METAL	1	PRIMED	LAUNDRY DOOR: SELF-CLOSING, SELF-LATCHING, STAINLESS, BOTTOM-HINGE, RUBBER SAFETY BAFFLE
D10	MEN'S LOCKERS	1'-6"	1'-6"	1 3/4"	A	WOOD	90	OSWALD			METAL	1	PRIMED	LAUNDRY DOOR: SELF-CLOSING, SELF-LATCHING, STAINLESS, BOTTOM-HINGE, RUBBER SAFETY BAFFLE
D11	MEN'S BATHROOM	3'-0"	7'-0"	1 3/4"	A	WOOD	20				METAL	1	PRIMED	
D12	MEN'S LOCKERS	(2) 1'-2"	7'-0"	1 3/4"	A	WOOD	20				METAL	1	PRIMED	DOUBLE DOORS. 2'-4" TOTAL WIDTH
D13	MEN'S BATHROOM							EXISTING DOOR					PRIMED	REPLACE EXISTING LOCKSET/HANDLE W/ NEW PUSH BOTTON DIGITAL LOCK
D14	MEN'S LOCKERS							EXISTING DOOR					PRIMED	REPLACE EXISTING LOCKSET/HANDLE W/ NEW PUSH BOTTON DIGITAL LOCK

ROOM FINISH SCHEDULE

ROOM #	ROOM NAME	FLOOR	BASE	NORTH	EAST	SOUTH	WEST	CEILING	NOTES
004	BATHROOM	SEALED CONCRETE	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	PAINTED - TYPE C1	2-HR, SEE A3.1
005	BATHROOM	SEALED CONCRETE	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	PAINTED - TYPE C1	2-HR, SEE A3.1
006	VACUUM BOOTH	SEALED CONCRETE	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	BLOCK FILLER PRIMER ON CMU, BOTH SIDES
007	SOILED PPE ROOM	SEALED CONCRETE	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	BLOCK FILLER PRIMER ON CMU, BOTH SIDES
103	CLEAN LINEN	VCT	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	EXPOSED CONSTRUCTION	
105	MEN'S LOCKERS	CT-1	CERAMIC	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	SEE 6/A3.1 FOR TYPICAL LOCKERS ELEVATION
106	VENDING	VCT	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	
107	LUNCH ROOM	VCT	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	SEE A2.1 FOR ADA ELEVATIONS
108	LOUNGE	VCT	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	SEE A2.1 FOR ADA ELEVATIONS
111	CORRIDOR	VCT	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	ACT/PAINTED	
112	MEN'S BATHROOM	CT-1	CERAMIC	PAINTED	PAINTED	PAINTED	PAINTED	ACT	
113	LAUNDRY	VCT	VINYL	PAINTED	PAINTED	PAINTED	PAINTED	PAINTED	
114	SHOWER ROOM	CT-2	CERAMIC	CTW	CTW	CTW	CTW	PAINTED	

MATERIAL LEGEND

MATERIAL	KEY NAME	MANUFACTURER	STYLE/COLOR
ACOUSTICAL CEILING TILE 2'x2'	ACT	ARMSTRONG	CONTRACTOR SERIES, 934 RANDOM TEXTURED, ANGLED TEGULAR EDGE, W/ WHITE GRID
FLOORING	CT-1	TBD BY OWNER	12"x12" CERAMIC TILE FLOORING. COLOR TBD BY OWNER
	CT-2	TBD BY OWNER	2"x2" MOSAIC CERAMIC TILE FLOORING. COLOR TBD BY OWNER
	CT-3	DALTILE	6"x6" ABRASIVE ECO-BODY CERAMIC NATURAL HUE FIELD TILE CAP. COLOR DAISY QH97 (2)
	VCT	ARMSTRONG	12"x12" CHROMASPIN. COLOR TBD BY OWNER
WALL BASE	VINYL	JOHNSONITE	4" TOE COVED VINYL BASE. COLOR TBD BY OWNER
	CERAMIC	TBD BY OWNER	CERAMIC TILE COVE BASE. COLOR TBD BY OWNER
WALL	CTW	TBD BY OWNER	6"x6" CERAMIC WALL TILE. COLOR TBD BY OWNER
	PTD-1	SHERWIN WILLIAMS	COLOR TO BE DETERMINED BY OWNER
PAINT	PTD-2	SHERWIN WILLIAMS	COLOR TO BE DETERMINED BY OWNER
	PTD-3	SHERWIN WILLIAMS	COLOR TO BE DETERMINED BY OWNER
	PTD-4	SHERWIN WILLIAMS	COLOR TO BE DETERMINED BY OWNER

ecomaine
LOCKER ROOM RENOVATION
 PORTLAND
 MAINE

SIGNED COPY OF DRAWING ON FILE AT DIRIGO A/E OFFICE

6/1/16

SCHEDULES

REV.	DATE	DESCRIPTION	CHECKED BY:
1	1/18/16	ISSUED FOR CONSTRUCTION	TWP
2	6/1/16	ISSUED FOR SI #1	TWP
3			TWP

PH: (207) 225 - 3040
 1071 Auburn Road
 Suite G
 Turner, ME 04282

DIRIGO ARCHITECTURAL
 ENGINEERING • CONSTRUCTION MANAGEMENT
 EMail: tperkins@dirigoae.com W: www.dirigoae.com

DATE: 6/1/16
 PROJECT NO. 15-015
 SHEET NO.
A0.2