Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 05/17/17

NOTES:

1. SEE SHEET E–001 FOR LEGEND, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE SHEET E–601 FOR LIGHTING FIXTURE SCHEDULE AND PANEL SCHEDULE.

KEYED NOTES:

1. SURFACE MOUNTED FIXTURE.
2. RECONNECT SALVAGED SUPPLY CONDUCTORS FROM DESIGNATED PANEL LP9 CIRCUIT. REPLACE LAMPS; SEE SHEET E–601 FOR EXISTING FIXTURE PRODUCT DATA. NOTE: FIXTURE LOCATION NOT SHOWN TO SCALE; SEE SHEET C–101 FOR EXACT FIXTURE LOCATION.
3. SWITCH CONTROLS INTERIOR LIGHTING FIXTURES IN VESTIBULE, KITCHEN, AND OFFICE.

CIRCUIT SCHEDULE:

1. LP9–1
2. LP9–2
3. LP9–27,29

LIGHTING FLOOR PLAN

SCALE: 1/2" = 1'–0"

PROJECT NORTH

0 1' 2' 4'
Scale: 1/2" = 1'–0"

ISSUED FOR BID
NOT FOR CONSTRUCTION
JANUARY 5, 2017

STATE OF MAINE
MATTHEW R. LYLE
No. 11695
LICENSED
PROFESSIONAL ENGINEER
01-05-17

REV	DESCRIPTION	DWN	APP	DATE
C	RE-ISSUED FOR BID	MRL	CBC	01/05/17
B	RE-ISSUED FOR BID	MRL	CBC	10/28/16
A	ISSUED FOR BID	MRL	CBC	9/02/16

ecomaine
64 BLUEBERRY ROAD, PORTLAND, ME

SCALE HOUSE WITH INSULATED BLOCK CONSTRUCTION

LIGHTING FLOOR PLAN

PLEASE NOTE: THIS DOCUMENT MAY NOT ACCURATELY REPRESENT THE FINAL DOCUMENT. ONLY AN ENGINEER, ARCHITECT OR SURVEYOR SIGNED, SEALED AND DATED PAPER COPY, PROVIDED BY THIS OFFICE, MAY BE UTILIZED FOR BIDDING OR CONSTRUCTION PURPOSES.

Colby Company engineering
47A York Street
Portland, Maine 04101
207.553.7753
colbycoengineering.com

SIZE: ANSI D
DATE: 09/02/2016
DES BY: MRL
DWN BY: MRL
CKD BY: CBC

PROJECT NO. 162.002.002
SHEET 39 OF 40

DRAWING NO. E-102

X:\162 EcoMaine\162.002.002 - Scale House with CMU\Drawings\Sheets\E-102.dwg - 1/5/2017 2:33 PM - ZACH JONES