Reviewed for Code Compliance
Inspections Division
Date: 05/17/17

NOTES:

1. SEE SHEET M-001 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

KEYED NOTES:

1. ROUTE TWO (2) SETS OF INSULATED 3/8" GAS PIPING & 1/4" LIQUID PIPING FROM CU-1 DOWN THRU ROOF TO HP-1 & HP-2. INSTALL IN PROTECTIVE SLEEVE AND COORDINATE FLASHING DETAIL WITH ARCHITECTURAL.

MECHANICAL ROOF PLAN

SCALE: 1/2" = 1'-0"

PROJECT NORTH

0 1' 2' 4'
Scale: 1/2" = 1'-0"

ISSUED FOR BID
NOT FOR CONSTRUCTION
JANUARY 5, 2017

STATE OF MAINE
EMILY PINYARD
No. 12126
LICENSED
PROFESSIONAL ENGINEER
01/05/17

REV	DESCRIPTION	DWN	APP	DATE
C	RE-ISSUED FOR BID	MBD	ERP	01/05/17
B	RE-ISSUED FOR BID	MBD	ERP	10/28/16
A	ISSUED FOR BID	MBD	ERP	9/02/16

ecomaine
64 BLUEBERRY ROAD, PORTLAND, ME

SCALE HOUSE WITH INSULATED BLOCK CONSTRUCTION

MECHANICAL ROOF PLAN

PLEASE NOTE: THIS DOCUMENT MAY NOT ACCURATELY REPRESENT THE FINAL DOCUMENT. ONLY AN ENGINEER, ARCHITECT OR SURVEYOR SIGNED, SEALED AND DATED PAPER COPY, PROVIDED BY THIS OFFICE, MAY BE UTILIZED FOR BIDDING OR CONSTRUCTION PURPOSES.

Colby Company engineering
47A York Street
Portland, Maine 04101
207.553.7753
colbycoengineering.com

SIZE: ANSI D
DATE: 09/02/2016
DES BY: MIF
DWN BY: MBD
CKD BY: ERP

PROJECT NO. 162.002.002
SHEET 29 OF 40

DRAWING NO. M-102

X:\162 EcoMaine\162.002.002 - Scale House with CMU\Drawings\Sheets\M-102.dwg - 1/5/2017 2:30 PM - ZACH JONES