



NOTES:

1. THE CHANGES INDICATED ON THIS SKETCH ARE ASSOCIATED WITH THE RELOCATION OF THE MAIN ENTRANCE.
2. BID ALTERNATE: CONTRACTOR SHALL ALSO PRICE AN ALTERNATE FOR 60 LF OF 18" REINFORCED CONCRETE PIPE IN PLACE OF HDPE CALLED OUT ABOVE.
3. RIPRAP PLUNGE POOLS IN THIS SKETCH HAVE BEEN SHOWN LARGER THAN INDICATED IN THE THE DETAILS IN THE ORIGINAL CONSTRUCTION DOCUMENTS DUE TO OBSERVED EROSION IN THE EXISTING DITCH AROUND THE ENTRANCE. RIPRAP PLUNGE POOLS SHALL BE CONSTRUCTED AS INDICATED ON THIS SKETCH.

FOR PRICING