Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/18/13

FLOOR PLAN
1/8" = 1'-0"
A1

ROBERT J. FOSTER – ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761–3822

REGISTERED ARCHITECT ROBERT J. FOSTER #1734 STATE OF MAINE

6/18/13

Project Title

CROSS INSURANCE RENOVATIONS

2331 CONGRESS STREET
Portland, Maine

LEGEND

#	PARTITION TYPE MARKER SEE A40.1 FOR DETAILS
#	DOOR NUMBER SEE A60.1 FOR DOOR SCHEDULE
NAME #	ROOM NAME AND NUMBER SEE A60.2 FOR FINISH SCHEDULES
FEC & FE	FIRE EXTINGUISHER CABINETS & SURFACE MTD FIRE EXTINGUISHERS
#	CASEWORK TYPE MARKER SEE DETAIL B4 ON SHT. A60.2

GENERAL NOTES

1. ALL DIMENSIONS ARE EITHER TO FACE OF STUDS OR CENTER LINE OF STUDS UNLESS OTHERWISE NOTED.
2. PROVIDE SOLID BLOCKING AT WALLS TO SUPPORT ALL REQUIRED ITEMS: GRAB BARS, HANDRAILS, CABINETS, STORAGE SHELVING, ETC...
3. REPAIR ALL WALLS AND CEILINGS DAMAGED DURING DEMOLITION TO MATCH SURROUNDING FINISHES.

Mark	Date	Description
1	06–12–13	REVISIONS
	03–29–13	ISSUED FOR BID

Issue Dates

Drawing Title

FLOOR PLAN

Drawing Number

A10.1