Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/18/13

DOOR AND FRAME SCHEDULE

NO.	DOOR SIZE WIDTH	DOOR SIZE HEIGHT	DOOR SIZE THICK.	DOOR MAT	DOOR TYPE	DOOR GLASS	DOOR LOUVER WIDTH	DOOR LOUVER HEIGHT	FRAME MAT	FRAME TYPE	FRAME DETAILS HEAD	FRAME DETAILS JAMB	FRAME DETAILS SILL	FIRE RATING		REMARKS
102																EXISTING TO REMAIN
103	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	STEEL	3	E1	D1	---	1 HOUR		CLOSER
104	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
105	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
108	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
109	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
110	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
112	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
113	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
114	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
117	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
118	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
119	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
120	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			
121A	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			CLOSER
121B	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			CLOSER
121C	3'-0"'	7'-0"	1 3/4"	ALUM.	D	---	---	---	ALUM.	4	E2	D2	ALUM.			CLOSER
122	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	2	B1	A1	---			
123	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			
124	3'-0"'	7'-0"	1 3/4"	WOOD	B	TEMP	---	---	WOOD	1	B1	A1	---			
125	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			
126	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			
128	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			CLOSER
129	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			CLOSER
130	3'-0"'	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			CLOSER
131	3'-0"	7'-0"	1 3/4"	WOOD	A	---	---	---	WOOD	1	B1	A1	---			CLOSER
132	3'-0"	7'-0"	1 3/4"	WOOD	C	TEMP	---	---	WOOD	5	B1	A1	---			CLOSER

ALUMINUM FRAME HEAD — 1 1/2" = 1'-0" — E2

STEEL FRAME HEAD — 1 1/2" = 1'-0" — E1

ALUMINUM FRAME JAMB — 1 1/2" = 1'-0" — D2

STEEL FRAME JAMB — 1 1/2" = 1'-0" — D1

WOOD FRAME JAMB — 1 1/2" = 1'-0" — C2

WOOD FRAME JAMB — 1 1/2" = 1'-0" — C1

DOOR TYPES — 1/4" = 1'-0" — B3

WOOD FRAME HEAD — 1 1/2" = 1'-0" — B2

WOOD FRAME HEAD — 1 1/2" = 1'-0" — B1

FRAME TYPES — 1/4" = 1'-0" — A3

WOOD FRAME SILL — 1 1/2" = 1'-0" — A2

WOOD FRAME JAMB — 1 1/2" = 1'-0" — A1

ROBERT J. FOSTER – ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT ROBERT J. FOSTER 01734 STATE OF MAINE
3-29-13

Project Title

CROSS INSURANCE RENOVATIONS

2331 CONGRESS STREET
Portland, Maine

Mark	Date	Description
	03-29-13	ISSUED FOR BID

Issue Dates

Drawing Title

DOOR SCHEDULE AND DETAILS

Drawing Number

A60.1