Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/18/13

ROOM FINISH SCHEDULE

ROOM		FLOOR		BASE		WAINSCOT			WALLS								CEILING			REMARKS
NO.	NAME	MAT	FIN	MAT	FIN	MAT	FIN	HT	NORTH	FIN	EAST	FIN	SOUTH	FIN	WEST	FIN	MAT	FIN	HT	
102	RECEPTION	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT/GPDW	PT	9'-0	CHAIR RAIL – SEE DETAIL E1
103	UTILITY ROOM	CONC		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
104	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
105	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
106	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-0	
107	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
108	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
109	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
110	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
111	OPEN OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
112	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
113	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
114	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
115	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
116	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
117	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
118	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
119	BREAK ROOM	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
120	CLOSET	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
121	EXIT ACCESS	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
122	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
123	FILE ROOM	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
124	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
125	WORK ROOM	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
126	CONFERENCE RM	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	CHAIR RAIL – SEE DETAIL E1
127	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	8'-0	
128	M. TOILET RM	CERAMIC TILE		CERAMIC TILE		CERAMIC TILE		48"	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
129	W. TOILET RM	CERAMIC TILE		CERAMIC TILE		CERAMIC TILE		48"	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
130	M. TOILET RM	CERAMIC TILE		CERAMIC TILE		CERAMIC TILE		48"	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
131	W. TOILET RM	CERAMIC TILE		CERAMIC TILE		CERAMIC TILE		48"	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'-0	
132	OPEN								GPDW		GPDW		GPDW		GPDW					UNFINISHED

TYP. EXTERIOR WALL — 1 1/2" = 1'-0" — C2

CHAIR RAIL DTL. — 3" = 1'-0" — E2

TYP. WOOD BASE — 3" = 1'-0" — D2

COUNTER DTL. — 1 1/2" = 1'-0" — C1

1 BREAK RM ELEV. 2 WORK RM ELEV. 3 WORK RM ELEV.

CASEWORK ELEVATIONS — 1/4" = 1'-0" — B4

WAINSCOT TILE PATTERN — 1/2" = 1'-0" — B3

CASEWORK DTL — 3/4" = 1'-0" — A2

CASEWORK DTL — 3/4" = 1'-0" — B1

CASEWORK DTL — 3/4" = 1'-0" — A1

3 DESK PLAN

2 DESK ELEV. 3 DESK ELEV. 4 DESK ELEV.

RECEPTION DESK — 1/4" = 1'-0" — A3

ROBERT J. FOSTER – ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT ROBERT J. FOSTER #1734 STATE OF MAINE
3-27-13

Project Title

CROSS INSURANCE RENOVATIONS

2331 CONGRESS STREET
Portland, Maine

Mark	Date	Description
	03-29-13	ISSUED FOR BID

Issue Dates

Drawing Title

ROOM FINISH SCHEDULE AND DETAILS

Drawing Number

A60.2